

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400356858

Date Received:

12/19/2012

PluggingBond SuretyID

20090078

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐Refiling ☐Sidetrack ☐

3. Name of Operator: PDC ENERGY INC

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Liz Lindow Phone: (303)831-3974 Fax: ()

Email: liz.lindow@pdce.com

7. Well Name: Thornton Well Number: 11V-404

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 12049

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 11 Twp: 7N Rng: 66W Meridian: 6

Latitude: 40.593830 Longitude: -104.736800

Footage at Surface: 1298 feet FNL/FSL FNL 534 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4961 13. County: WELD

14. GPS Data:

Date of Measurement: 09/20/2012 PDOP Reading: 1.8 Instrument Operator's Name: Thomas Carlson

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
1520 FNL 500 FEL 1520 FNL 500 FWL
Sec: 11 Twp: 7N Rng: 66W Sec: 11 Twp: 7N Rng: 66W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 276 ft

18. Distance to nearest property line: 266 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 460 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CDLL		320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

N2, W2SW of Section 11 T7N R66W 6th PM

25. Distance to Nearest Mineral Lease Line: 500 ft

26. Total Acres in Lease: 465

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	875	830	875	0
1ST	8+3/4	7+26/0	26	0	8,064	650	8,064	500
1ST LINER	6+1/8	4+1/2	11.6	6748	12,049			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments 7" casing string will be cemented to at least 200' above Niobrara, around 500' from surface. CBL will not be run. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waivers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 320 acres, N2 of Sec 11 T7N R66W. Proposed spacing unit map and 30-day certificate is attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Liz Lindow

Title: Regulatory Analyst Date: 12/19/2012 Email: liz.lindow@pdce.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTO' located at: W:\netpub\Net\Reports\policy_nto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400356868	WELL LOCATION PLAT
400356869	DEVIATED DRILLING PLAN
400356871	DIRECTIONAL DATA
400356872	30 DAY NOTICE LETTER
400356905	PROPOSED SPACING UNIT
400361503	EXCEPTION LOC REQUEST
400361504	EXCEPTION LOC WAIVERS

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)