

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400353244

Date Received:

12/19/2012

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Matt Barber

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 606-4385

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-21020-00

6. County: GARFIELD

7. Well Name: Patterson

Well Number: SG 433-27

8. Location: QtrQtr: SESW Section: 27 Township: 7S Range: 96W Meridian: 6

Footage at surface: Distance: 1180 feet Direction: FSL Distance: 1875 feet Direction: FWL

As Drilled Latitude: 39.404485 As Drilled Longitude: -108.098551

## GPS Data:

Data of Measurement: 12/21/2012 PDOP Reading: 2.1 GPS Instrument Operator's Name: J. Kirkpatrick

\*\* If directional footage at Top of Prod. Zone Dist.: 1927 feet. Direction: FSL Dist.: 2086 feet. Direction: FEL

Sec: 27 Twp: 7S Rng: 96W

\*\* If directional footage at Bottom Hole Dist.: 1927 feet. Direction: FSL Dist.: 2068 feet. Direction: FEL

Sec: 27 Twp: 7S Rng: 96W

9. Field Name: GRAND VALLEY

10. Field Number: 31290

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 04/23/2012 13. Date TD: 04/26/2012 14. Date Casing Set or D&amp;A: 04/27/2012

## 15. Well Classification:

☐ Dry ☐ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 5432 TVD\*\* 5060 17 Plug Back Total Depth MD 5374 TVD\*\* 5002

18. Elevations GR 5013 KB 5039

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

MUD LOG; CBL

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18+1/4	48	0	71	37	0	71	VISU
SURF	13+1/2	9+5/8	32.3	0	1,298	350	0	1,298	VISU
1ST	7+7/8	4+1/2	11.6	0	5,407	890	2,575	5,407	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
MESAVERDE	2,486		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	4,755		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	5,260		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to big rig spud date.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Matt Barber

Title: Sr. Regulatory Specialist Date: 12/19/2012 Email: matt.barber@wpenergy.com

**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400360303	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400360301	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400353244	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400360312	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments****User Group      Comment      Comment Date**

--	--	--

Total: 0 comment(s)