

Map Unit Description

Lincoln County, Colorado

112 Bankard-Glenberg complex, 0 to 3 percent slopes, occasionally flooded

Setting

Elevation: 4400 to 6000 feet
Mean annual precipitation: 11 to 16 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 155 days

Composition

Bankard, occasionally flooded, and similar soils: 55 percent
Glenberg, occasionally flooded, and similar soils: 30 percent
Minor components: 15 percent

Description of Bankard, occasionally flooded

Setting

Landform: Flood plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium

Properties and Qualities

Slope: 0 to 3 percent
Drainage class: Somewhat excessively drained
Capacity of the most limiting layer to transmit water (Ksat): High or very high (6.00 to 19.99 in/hr)
Frequency of flooding: Occasional
Frequency of ponding: None
Calcium carbonate maximum: 5 percent
Gypsum maximum: 0 percent
Available water capacity: Low (about 3.6 inches)

Interpretive Groups

Land capability (non irrigated): 6s
Ecological site: Sandy Bottomland (R067BY031CO)

Typical Profile

0 to 5 inches: loamy sand
5 to 60 inches: loamy sand

Description of Glenberg, occasionally flooded

Setting

Landform: Flood plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Alluvium

Properties and Qualities

Slope: 0 to 3 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Frequency of flooding: Occasional
Frequency of ponding: None
Calcium carbonate maximum: 5 percent
Gypsum maximum: 0 percent
Available water capacity: Low (about 5.9 inches)

Interpretive Groups

Land capability (non irrigated): 3e
Ecological site: Sandy Bottomland (R067BY031CO)

Typical Profile

0 to 3 inches: fine sandy loam
3 to 32 inches: fine sandy loam
32 to 60 inches: loamy sand

Minor Components

Map Unit Description

Lincoln County, Colorado

Haverson soils

Percent of map unit: 4 percent

Landform: Flood plains

Ecological site: Overflow Central/South - Draft (R067XY036CO)

Karval soils

Percent of map unit: 4 percent

Landform: Hills

Other vegetative classification: GRAVEL BREAKS (067XY063CO_1)

Seldom soils

Percent of map unit: 3 percent

Landform: Flood plains

Other vegetative classification: Salt Meadow (069XY030CO_1)

Orsa soils

Percent of map unit: 3 percent

Landform: Flood plains

Gravel pits

Percent of map unit: 1 percent

Map Unit Description

Lincoln County, Colorado

194 Valent-Bijou complex, 1 to 12 percent slopes

Setting

Elevation: 4400 to 6000 feet
Mean annual precipitation: 11 to 16 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 135 to 155 days

Composition

Valent and similar soils: 55 percent
Bijou and similar soils: 30 percent
Minor components: 15 percent

Description of Valent

Setting

Landform: Dunes
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Eolian sands

Properties and Qualities

Slope: 1 to 12 percent
Drainage class: Excessively drained
Capacity of the most limiting layer to transmit water (Ksat): High or very high (6.00 to 19.99 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 0 percent
Gypsum maximum: 0 percent
Available water capacity: Low (about 4.2 inches)

Interpretive Groups

Land capability (non irrigated): 6e
Ecological site: Deep Sand (R067BY015CO)

Typical Profile

0 to 3 inches: sand
3 to 60 inches: sand

Description of Bijou

Setting

Landform: Interdunes
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Eolian deposits

Properties and Qualities

Slope: 1 to 12 percent
Drainage class: Somewhat excessively drained
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 0 percent
Gypsum maximum: 0 percent
Available water capacity: Low (about 5.5 inches)

Interpretive Groups

Land capability (non irrigated): 6e
Ecological site: Sandy Plains (R067BY024CO)

Typical Profile

0 to 4 inches: loamy sand
4 to 9 inches: loamy sand
9 to 36 inches: sandy loam
36 to 60 inches: loamy sand

Map Unit Description

Lincoln County, Colorado

Minor Components

Apishapa soils

Percent of map unit: 4 percent

Landform: Depressions

Ecological site: Plains Swale (R067XY010CO)

Olneest soils

Percent of map unit: 4 percent

Landform: Hills

Other vegetative classification: SANDY PLAINS (067XY024CO_1)

Truckton soils

Percent of map unit: 3 percent

Landform: Hills

Other vegetative classification: Sandy Plains (069XY026CO_1)

Otero soils

Percent of map unit: 3 percent

Landform: Hills

Other vegetative classification: SANDY PLAINS (067XY024CO_1)

Gravel pits

Percent of map unit: 1 percent