

## BMP Plan

Wiepking-Fullerton Energy, L.L.C.  
4600 S. Downing St.  
Englewood, CO 80113  
303-789-1798  
303-761-9067 (fax)

Certification to Discharge  
Under  
CDPS General Permit COR-03000  
Stormwater Discharges Associated with Construction

Certification Number COR 39788

Kerry # 8 well  
T10S, R55W  
Sec. 20: NE1/4NE1/4  
Lincoln County, Colorado

### Description of Well Site and Construction Area

1-3 acre site with access road for drilling of oil and gas well. Terrain is flat with native grass and sagebrush. Surface Roughening will be used on low side of drill site to reduce speed of runoff, increase infiltration, reduce erosion, trap sediment and prepare soil for reseeded. A dirt berm will be placed on the North, East and West edge of the well pad to protect surface water located 70' North of well pad. No water or mud pits will be excavated. A closed loop system will be used for all water and drilling mud. Topsoil will be separated and spread on drill site as final operation before reseeded operations, which will be completed within 6 months weather permitting. After drilling operations are completed and to prevent soil erosion. The drill site will be disked and straw crimped in or manure spread.

Stormwater Management Plan (SWMP) is on file in Wiepking-Fullerton Energy, L.L.C. office.

Spill Prevention, Control and Countermeasure Plan is on file in Wiepking-Fullerton Energy, L.L.C. office.

Job: 10061 Kerry #8

Inv # 1921

High Prairie Surveying of Kiowa, Colorado has in accordance with a request from **Jack Fincham, Wiepking Fullerton Energy** has determined the location of **Kerry #8** to be **660 feet FNL**, and **660 feet FEL**, (90° off Section lines) of **SECTION 20**, Township **10s**, Range **55w** of the 6th Principal Meridian, **Lincoln County**, Colorado.

Date: Staked on 5-04-12 drawn on 5-05-12.

Re: Staked by Keith Westfall

Drawn: Drawn by Elijah Frane

# Topo Exhibit

WIEPKING FULLERTON  
NE ¼ SEC 20-10S-55W  
KERRY #8  
LINCOLN CO. COLORADO

