

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

1714571

Date Received:

04/20/2009

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: KATE SHIRLEY

2. Name of Operator: NOBLE ENERGY INC

Phone: (281) 876-6105

3. Address: 1625 BROADWAY STE 2200

Fax: (281) 876-2503

City: DENVER State: CO Zip: 80202

5. API Number 05-045-14753-00

6. County: GARFIELD

7. Well Name: SAVAGE

Well Number: 8-12C

8. Location: QtrQtr: NWNW Section: 8 Township: 7S Range: 94W Meridian: 6

Footage at surface: Distance: 1098 feet Direction: FNL Distance: 996 feet Direction: FWL

As Drilled Latitude: 39.456790 As Drilled Longitude: -107.916068

GPS Data:

Date of Measurement: 05/21/2009 PDOP Reading: 2.3 GPS Instrument Operator's Name: DAN MORBY

** If directional footage at Top of Prod. Zone Dist.: 2119 feet. Direction: FNL Dist.: 569 feet. Direction: FWL

Sec: 8 Twp: 7S Rng: 94W

** If directional footage at Bottom Hole Dist.: 2117 feet. Direction: FNL Dist.: 526 feet. Direction: FWL

Sec: 8 Twp: 7S Rng: 94W

9. Field Name: RULISON

10. Field Number: 75400

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 08/09/2008 13. Date TD: 08/21/2008 14. Date Casing Set or D&A: 08/22/2008

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 9336 TVD** 9231 17 Plug Back Total Depth MD 9286 TVD** 9181

18. Elevations GR 6777 KB 6801

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, RMT

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	20			0	104		0	104	CALC
SURF	12+1/4	8+5/8		0	1,527	330	0	1,527	CALC
1ST	7+7/8	4+1/2		0	9,325	692	4,810	9,325	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	5,602		<input type="checkbox"/>	<input type="checkbox"/>	TOG: MEASURED DEPTH: TOP: 6562
CAMEO	7,890		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	8,792		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Y _____

Print Name: KATE SHIRLEY _____

Title: REGULATORY _____

Date: _____

Email: KSHIRLEY@NOBLEENERGYINC.COM _____

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
	CMT Summary *	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
1787251	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	ON HOLD. CEMENT TICKETS REQUESTED. DHS	10/7/2010 7:35:16 AM

Total: 1 comment(s)