

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400367117

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JENNIFER LIND Phone: (720)876-5890 Fax: (720)876-6890

Email: JENNIFER.LIND@ENCANA.COM

7. Well Name: SG Well Number: 8509C-33 E34496

8. Unit Name (if appl): BIG JIMMY UNIT Unit Number: COC74105X

9. Proposed Total Measured Depth: 12678

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 34 Twp: 4S Rng: 96W Meridian: 6

Latitude: 39.659797 Longitude: -108.160631

Footage at Surface: 2284 feet FNL/FSL 986 feet FEL/FWL
FNL FWL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 8324 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/01/2012 PDOP Reading: 1.3 Instrument Operator's Name: ROBERT KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
1985 FSL 1302 FEL 1985 FSL 1302 FEL
Sec: 33 Twp: 4S Rng: 96W Sec: 33 Twp: 4S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3 mi

18. Distance to nearest property line: 2495 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 264 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC65556

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

PLEASE SEE ATTACHED MAP

25. Distance to Nearest Mineral Lease Line: 1302 ft

26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RECYCLE AND BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	LINE PIPE	0	120	176	120	0
SURF	12+1/4	9+5/8	36	0	2,500	782	2,500	0
1ST	7+7/8	4+1/2	11.6	0	12,678	1,364	12,678	7,697

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments PLEASE NOTE THAT ENCANA OIL & GAS (USA) INC. IS THE SURFACE OWNER FOR THIS LOCATION. #17 IS CALCULATED FROM NEAREST BUILDING. SURFACE CASING HOLE SIZE WILL BE 14-3/4", 12-1/4" OR 13-1/2". CONDUCTOR CASING WILL BE CEMENTED TO SURFACE. PRODUCTION CASING WILL BE CEMENTED 200 INTO THE SURFACE CASING.

34. Location ID: 335928

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: _____ Email: JENNIFER.LIND@ENCANA.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTO' located at: W:\netpub\Net\Reports\policy_nto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400367129	DEVIATED DRILLING PLAN
400367130	WELL LOCATION PLAT
400367133	FED. DRILLING PERMIT
400367136	DIRECTIONAL DATA
400367138	MINERAL LEASE MAP
400367142	TOPO MAP

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)