



# SURFACE CASING AND CEMENTING REPORT

Well Name:	Logan 2H
County	Weld
State	Colorado

## Surface casing

Run Date	12/1/2012
Size:	9 5/8"
Set at	996' KB
Hole Size	13 1/2"
Joints Run	24
Hours to Run Casing	3

## Casing String Details

Number	Description	Wt/ft	Grade	Threads	Condition	Length	Depth
1	Float Shoe	36.00	N-80	STC	New	0.80	996.00
2	Shoe Joint, 9 5/8", 36#, J55, STC	36.00	J-55	STC	New	42.13	953.87
3	Float Collar	36.00	N-80	STC	New	1.00	952.87
4	Casing, 9 5/8", 36#, J55, STC	36.00	J-55	STC	New	952.87	0.00

## Centralizers

Number	5
Type	Bow Spring 9 5/8" X 13.5"
Placement Joints	2, 5, 9, 13, 17

## Cement Details

Service Company	Cementers Inc
-----------------	---------------

Preflush	30 bbl fresh water
Lead	670 sx, 1.18cf/sx, 15.2ppg, 140.8 bbl
Tail	none
Displacement	73.7 bbl fresh water

Notes	Bumped plug
	Floats Held
	Circulated 6 bbls cement to surface