



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601092

Date	10-3-12	Well Owner	Kerr McGee	Well No.	3A2-28112	Lease	121155
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (main floor - 40)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Fl. 940			
Surface	9 7/8" CSG - 364" - 135" H ₂ O		Bottom of Surface	Fl. 934			
Plug			Plug Landed @	880	Fl.	Time On 0545	
Production			Pipe Landed @	924	Fl.	Plug Down 0930	
Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat TYPE III	700	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Cete 1/4 # Per Sack							
Mileage Charge	1.32	Miles					
Fuel Surcharge	1.32	MILES					
Additional Cement		SKS					
Mixing Rate	4 BPM	Pre-Flush	0824	0832			
Disp. Rate	5 BPM	Mixing	0832	0913			
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0913	0916			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0916	0930			
Water/Cement	6.25 Gal/SK						
Water Temp.	59°F						
Total Slurry Vol.	1164.5	BBLS Cement					
Landed Plug @	800	PSI/Final Lift @ 300	PSI				
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total				
Displace W/ 68.8	BBLS H ₂ O	State CO 2.9%	Tax				
Circulate 4	BBLS Cement		Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1200		Pump Truck		44			
1207/1218		Bulk Truck		44/44			2063622

80012090

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe JOSH, ERNIE

Received By Randy Kade
Customer or His Agent