

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400364230

Date Received:

01/09/2013

PluggingBond SuretyID

20040083

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: PIONEER NATURAL RESOURCES USA INC

4. COGCC Operator Number: 10084

5. Address: 1401 17TH ST STE 1200

City: DENVER State: CO Zip: 80202

6. Contact Name: DeAnne Spector Phone: (303)928-7128 Fax: ()

Email: dspector@petro-fs.com

7. Well Name: Long View Farm Well Number: 33-19

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6950

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 19 Twp: 16S Rng: 53W Meridian: 6

Latitude: 38.645222 Longitude: -103.383664

Footage at Surface: 2167 feet FNL/FSL 2567 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4876 13. County: LINCOLN

14. GPS Data:

Date of Measurement: 11/12/2012 PDOP Reading: 1.2 Instrument Operator's Name: Ben Hardenbergh

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft

18. Distance to nearest property line: 2567 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 3 mi

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Atoka	ATOK	unspaced		
Cherokee	CHRK	unspaced		
Marmaton	MRTN	unspaced		
Mississippian	MSSP	unspaced		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 2004084

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T16S-R53W, Sec. 19: Lots 1, 2, 3, 4, E/2W/2, E/2

25. Distance to Nearest Mineral Lease Line: 2167 ft 26. Total Acres in Lease: 629

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Reserve Pit, pit will be lined

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	16	13+3/8		0	80		80	0
SURF	12+1/4	8+5/8	32	0	3,010	2,070	3,010	0
1ST	7+7/8	5+1/2	17	0	6,950	930	6,950	0

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments

34. Location ID:

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: DeAnne Spector

Title: Regulatory Analyst Date: 1/9/2013 Email: dspector@petro-fs.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy_NTC' located at: W:\Intsub\Net\Reports\policy_ntr.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400364230	FORM 2 SUBMITTED
400365969	WELL LOCATION PLAT
400366448	30 DAY NOTICE LETTER

Total Attach: 3 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

Type	Comment
Site Specific	Keep well site location, road and pipeline easement free of noxious weeds, litter and debris. Spray for noxious weeds and implement dust control as needed. Operator will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land. Construct and maintain gates where any roads used by operator, its employees or contractors cross through fences on the leased premises.
Construction	Remove only the minimum amount of vegetation necessary for the construction of roads and facilities. Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation. No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.
Interim Reclamation	Utilize only such area around each producing well as is reasonably necessary. Restore the remainder of the well site location to its original condition within a reasonable amount of time after the completion of operations. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.
Final Reclamation	All surface restoration shall be accomplished to the satisfaction of the Owner. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner. Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC).
Drilling/Completion Operations	The drilling pit will be lined.

Total: 5 comment(s)