

FORM 5A

Rev 06/12

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Table with columns DE, ET, OE, ES

Document Number: 400357852

Date Received: 12/14/2012

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Eileen Roberts
Phone: (303) 2284330
Fax: (303) 2284286

5. API Number 05-123-34676-00
6. County: WELD
7. Well Name: TOBY C
Well Number: 12-79HN
8. Location: QtrQtr: SESE Section: 2 Township: 4N Range: 64W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 04/26/2012 End Date: 04/26/2012 Date of First Production this formation: 05/08/2012

Perforations Top: 7179 Bottom: 11664 No. Holes: 0 Hole size: 0

Provide a brief summary of the formation treatment: Open Hole: []

Frac'd the Niobrara w/ 138,026 gals of Silverstim and Slick Water with 4222352#'s of Ottawa sand.

This formation is commingled with another formation: [] Yes [X] No

Total fluid used in treatment (bbl): 68635 Max pressure during treatment (psi): 3840
Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43
Type of gas used in treatment: Min frac gradient (psi/ft): 0.83
Total acid used in treatment (bbl): 0 Number of staged intervals: 21
Recycled water used in treatment (bbl): 2882679 Flowback volume recovered (bbl): 5571738
Fresh water used in treatment (bbl): 2689059 Disposition method for flowback: RECYCLE
Total proppant used (lbs): 4222352 Rule 805 green completion techniques were utilized: [X]

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/11/2012 Hours: 24 Bbl oil: 295 Mcf Gas: 527 Bbl H2O: 341
Calculated 24 hour rate: Bbl oil: 295 Mcf Gas: 527 Bbl H2O: 341 GOR: 1786
Test Method: FLOWING Casing PSI: 2530 Tubing PSI: 1530 Choke Size: 018/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1330 API Gravity Oil: 54
Tubing Size: 2 + 7/8 Tubing Setting Depth: 6898 Tbg setting date: 05/05/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: [] Yes [] No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: 12/14/2012 Email: eroberts@nobleenergyinc.com
:

Attachment Check List

Att Doc Num	Name
400357852	FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Off hold form 5 approved.	1/14/2013 3:10:10 PM
Permit	On Hold pending form 5 approval.	12/19/2012 12:11:31 PM

Total: 2 comment(s)