



CEMENTER'S WELL SERVICE, INC.  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601150

Date	11/10/2012	Well Owner	Kerr McGee	Well No.	290-542	Lease	RECHOLS
County	LOVELL	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAYBE 4)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	841		
Surface	99' 11" 150' 3" 13 1/2' 4016	Bottom of Surface		Fl.	832		
Plug		Plug Landed @	791	Fl.	Time On	1900	
Production		Pipe Landed @	827	Fl.	Plug Down	0145	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	120	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	120	Miles		
Fuel Surcharge	120	miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	2048	2054
Disp. Rate	5 BPM	Mixing	2054	2130
Slurry Vol.	1.32 Cu. Ft./SK	Change Valves	2130	2133
Slurry Wt.	14.8 - 15.0 PPG	Displacement	2133	2145
Water/Cement	6.25 Gal/SK			
Water Temp.	43			
Total Slurry Vol.	145.7	BBLS Cement		
Landed Plug @	800	PSI/Final Lift @	350	PSI
Pre-Flush W/	30	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	61.1	BBLS H <sub>2</sub> O	State	CO 2.9%
Circulate	4	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		40			
1214/1211		Bulk Truck		40/40			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM ADAM / TUCKER

Received By

Customer of His Agent