



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712


OUR INVOICE

601018

Date	8/26/12	Well Owner	Kerr McGee	Well No.	28N-11H2	Lessee	Weichel
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Fl. 938			
Surface	9 5/8" CSG-36"-12 1/4" Hole		Bottom of Surface	Fl. 931			
Plug	126' 9 5/8" CSG-36"		Plug Landed @	891	Fl.	Time On 1745	
Production	13 3/8" Conductor Pipe		Pipe Landed @	931	Fl.	Plug Down 2000	
Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat ✓ Type III	470	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Cete 1/4 # Per Sack							
Mileage Charge	88	Miles					
Fuel Surcharge	88	Miles					
Additional Cement		SKS					
Mixing Rate	4 BPM	Pre-Flush	1918	1924			
Disp. Rate	5 BPM	Mixing	1924	1943			
Slurry Vol.	1.32 ³ Cu.FL/Sk	Change Valves	1943	1946			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1946	2000			
Water/Cement	6.25 Gal/SK						
Water Temp.	70°F						
Total Slurry Vol.	110.4	BBLs Cement					
Landed Plug @	800	PSI/Final Lift @ 400	PSI				
Pre-Flush W/ 30	BBLs H ₂ O	Tax Reference Code	Sub Total				
Displace W/ 68.8	BBLs H ₂ O	State CO 2.9%	Tax				
Circulate 4	BBLs Cement		Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		44			
1217		Bulk Truck		44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Evan & Steve

Received By 
Customer or His Agent

80012090