



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601060

Date <u>9/2/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>35N-11422</u>	Lease <u>Weichel</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (MAJOR 44)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>930</u>	
Surface <u>9 5/8" CSC-36" 19 1/4 Hole</u>	Bottom of Surface	Fl. <u>923</u>	
Plug- <u>132' 9 5/8" CSC-36"</u>	Plug Landed @ <u>881</u>	FL	Time On <u>1045</u>
Production <u>13 3/8" Conductor Pipe</u>	Pipe Landed @ <u>923</u>	FL	Plug Down <u>1345</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III 100% EXCESS</u>	440	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	88	Miles		
Fuel Surcharge	88	Miles		
Additional Cement	30	SKS		
Mixing Rate 4 BPM	Pre-Flush	1303-	1309	
Disp. Rate 5 BPM	Mixing	1309-	1328	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	1328-	1331	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1331-	1345	
Water/Cement 6.25 Gal/SK				
Water Temp. 81°F				
Total Slurry Vol. 110.4	BBLS Cement			
Landed Plug @ 450	PSI/Final Lift @ 225	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 108.1	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLS Cement		Total	

Duaine Bell

Truck No.	Code	State Mileage	Nebraska	Colorado	Other	Total Mileage
1208		Pump Truck		44		
1914		Bulk Truck		44		

G/L Acct. 80012090

We do not assume any responsibility for any damages or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Evan & Steve

Received By Randy Dale
Customer or His Agent