

Well

Operator
Location
County
State
Field
Footages

Starks #1

North American Resources Co.
SWSW Section 30-T2N-R64W
Weld
Colorado
Wattenberg
1290' fsl, 1015' fwl

Log Tops

Base Fox Hills – 891'
Sussex – 4530'
Niobrara – 6856'
J Sand – 7610'

Spud: 5/25/1979
TD:
Rig Release:

Proposed cement plug
from surface - 950'

Surface Hole

12 1/4"

Surface Casing Cement

8 5/8" casing set at 213'.
Cemented with 225 sxs.
Cement circulated to surface

Production Casing

4 1/2" casing set at 7763'
Cemented with 225 sxs.

*1000 Angel at 738'

Main Hole

7-7/8" to TD

Proposed squeeze
holes @ 4530'

TOC 6830'

Proposed cement
plug from 6850' -7550'

Proposed CIBP
Set @ 7550'

J-Sand Perf

7618-52'
Frac'd with 309,200 #

7763' — TD

