

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400372571

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JENNIFER LIND Phone: (720)876-5890 Fax: (720)876-6890

Email: JENNIFER.LIND@ENCANA.COM

7. Well Name: SG Well Number: 8513D-27 L27496

8. Unit Name (if appl): BIG JIMMY UNIT Unit Number: COC74105X

9. Proposed Total Measured Depth: 12362

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 27 Twp: 4S Rng: 96W Meridian: 6

Latitude: 39.671033 Longitude: -108.160294

Footage at Surface: 1811 feet FNL/FSL 1080 feet FEL/FWL FSL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 8106 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 07/31/2012 PDOP Reading: 1.5 Instrument Operator's Name: ROBERT KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 482 FSL 1340 FWL 482 FSL 1340 FWL  
Bottom Hole: FNL/FSL 482 FSL 1340 FWL  
Sec: 27 Twp: 4S Rng: 96W Sec: 27 Twp: 4S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 16281 ft

18. Distance to nearest property line: 3719 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 264 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC68711

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

PLEASE SEE ATTACHED MAP

25. Distance to Nearest Mineral Lease Line: 482 ft 26. Total Acres in Lease: 160

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RECYCLE AND BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	LINE PIPE	0	120	176	120	0
SURF	12+1/4	9+5/8	36	0	2,500	782	2,500	0
1ST	7+7/8	4+1/2	11.6	0	12,362	1,318	12,362	7,108

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments PLEASE NOTE THAT ENCANA OIL & GAS (USA) INC. IS THE SURFACE OWNER FOR THIS LOCATION. #17 IS CALCULATED FROM NEAREST BUILDING. SURFACE CASING HOLE SIZE WILL BE 14-3/4", 12-1/4" OR 13-1/2". CONDUCTOR CASING WILL BE CEMENTED TO SURFACE.

34. Location ID: 335939

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: \_\_\_\_\_ Email: JENNIFER.LIND@ENCANA.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy\_NTO' located at: W:\Instrub\Net\Reports\policy\_nto.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400372576	TOPO MAP
400372577	MINERAL LEASE MAP
400372578	DEVIATED DRILLING PLAN
400372579	WELL LOCATION PLAT
400372581	FED. DRILLING PERMIT
400372582	DIRECTIONAL DATA

Total Attach: 6 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)