

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400373972

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

3. Name of Operator: PRONGHORN OPERATING LLC

4. COGCC Operator Number: 10422

5. Address: 8400 E PRENTICE AVENUE #1000

City: GREENWOOD State: CO Zip: 80111  
VILLAGE

6. Contact Name: Jake Flora Phone: (720)988-5375 Fax: ()

Email: jakeflora@kfrcorp.com

7. Well Name: UPRR #14-5 Well Number: 1X

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 5600

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 5 Twp: 14S Rng: 44W Meridian: 6

Latitude: 38.858170 Longitude: -102.367460

Footage at Surface: 662 feet FNL/FSL FSL 665 feet FEL/FWL FWL

11. Field Name: Cheyenne Wells Field Number: 11050

12. Ground Elevation: 4301 13. County: CHEYENNE

14. GPS Data:

Date of Measurement: 01/23/2013 PDOP Reading: 3.1 Instrument Operator's Name: Keith Westfall

15. If well is ☐ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 665 ft

18. Distance to nearest property line: 662 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 2615 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
LANSING	LNSNG			
MISSISSIPPIAN	MSSP			
TOPEKA	TOPK			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

ALL, SEC 5, 14S, 44W, 6th PM

25. Distance to Nearest Mineral Lease Line: 662 ft

26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: DRY & BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	17+1/2	13+3/8	54	0	400	200	400	0
1ST	12+1/4	8+5/8	24	0	1,700	100	1,700	1,200
S.C. 1.2						250	2,450	1,750
2ND	7+7/8	5+1/2	15.5	0	5,600	150	5,600	4,600
			Stage Tool		4,250	150	4,250	3,400

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments This is a rig skid and re-drill of the UPRR 14-5 wellbore. An attempt to re-enter the UPRR 14-5 proved unsuccessful due to an unpassable restriction in the hole at 1850'. Permitting and drilling the UPRR 14-5 1X will allow Pronghorn Operating LLC to test the original objectives while skidding the rig and utilizing the existing pits and location.

34. Location ID: 380119

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jake Flora

Title: Petroleum Engineer Date: \_\_\_\_\_ Email: jakeflora@kfrcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy\_NTO' located at: W:\netpub\Net\Reports\policy\_nto.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400374023	MINERAL LEASE MAP
400374024	SURFACE AGRMT/SURETY
400374026	PLAT

Total Attach: 3 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)