

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400310183

Date Received:

11/20/2012

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10261

4. Contact Name: JONATHAN RUNGE

2. Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION

Phone: (970) 669-7411

3. Address: 730 17TH ST STE 610

Fax: (970) 669-4077

City: DENVER State: CO Zip: 80202

5. API Number 05-123-35312-00

6. County: WELD

7. Well Name: COALBANK CREEK

Well Number: 9-20

8. Location: QtrQtr: NESE Section: 20 Township: 7N Range: 66W Meridian: 6

Footage at surface: Distance: 1722 feet Direction: FSL Distance: 196 feet Direction: FEL

As Drilled Latitude: 40.557819 As Drilled Longitude: -104.793338

## GPS Data:

Data of Measurement: 10/23/2012 PDOP Reading: 2.7 GPS Instrument Operator's Name: Bart Pfeifer

\*\* If directional footage at Top of Prod. Zone Dist.: 1983 feet. Direction: FSL Dist.: 687 feet. Direction: FEL

Sec: 20 Twp: 7N Rng: 66W

\*\* If directional footage at Bottom Hole Dist.: 1978 feet. Direction: FSL Dist.: 688 feet. Direction: FEL

Sec: 20 Twp: 7N Rng: 66W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 07/15/2012 13. Date TD: 07/19/2012 14. Date Casing Set or D&amp;A: 07/20/2012

## 15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7709 TVD\*\* 7662 17 Plug Back Total Depth MD 7676 TVD\*\* 7630

18. Elevations GR 4944 KB 4960

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

Density, Neutron, Induction, CBL

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	860	610	0	860	VISU
1ST	7+7/8	4+1/2	11.6	0	7,694	910	2,582	7,694	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____					
Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,904		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,622		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,039		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,192		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,460		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,504		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jonathan Runge

Title: Consultant Date: 11/20/2012 Email: jrunge@petersonenergy.com

### Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400310210	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400310190	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400310183	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400310191	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400347759	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400347761	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)