

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400374589

Date Received:

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling
Sidetrack

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Bonnie Lamond Phone: (720)876-5156 Fax: (720)876-6177

Email: bonnie.lamond@encana.com

7. Well Name: HMU Well Number: 6-13D (J6SEB)

8. Unit Name (if appl): Hunter Mesa Unit Number: COC055972
X

9. Proposed Total Measured Depth: 10291

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 6 Twp: 8S Rng: 92W Meridian: 6

Latitude: 39.387419 Longitude: -107.706082

Footage at Surface: 1933 feet FSL 1896 feet FEL
FNL/FSL FEL/FWL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 7143 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 12/17/2012 PDOP Reading: 1.4 Instrument Operator's Name: C.D. Slaugh

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 472 FSL 818 FWL Bottom Hole: 472 FSL 818 FWL
Sec: 6 Twp: 8S Rng: 92W Sec: 6 Twp: 8S Rng: 92W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 3471 ft

18. Distance to nearest property line: 703 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 330 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Iles | ILES | | | |
| Williams Fork | WMFK | | | |

21. Mineral Ownership: Fee State Federal Indian Lease #: COC51156

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 T8S-R92W Sec 5: Lots 3, 4, SWNW, W2SW Sec 6: Lots 3, 4, 5, 6, SE Sec 7: Lots 1, 2, 3, 4, E2 Sec 8: W2W2

25. Distance to Nearest Mineral Lease Line: 818 ft 26. Total Acres in Lease: 1172

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-----------|---------------|---------------|-----------|---------|---------|
| CONDUCTOR | 24 | 16 | .25" wall | 0 | 60 | 5 | 60 | 0 |
| SURF | 12+1/4 | 9+5/8 | 36 | 0 | 1,372 | 489 | 1,372 | 0 |
| 1ST | 7+7/8 | 4+1/2 | 11.6 | 0 | 10,291 | 1,079 | 10,291 | 0 |

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments The nearest distance is to a public road, ~3471 feet. Surface casing will run from 0'-200' with a hole size of 14-3/4 and casing size of 9-5/8. Surface casing will continue to run from 200'-1372' with a hole size of 12-1/4 and casing size of 9-5/8. Production casing will run from 0'-7127' with a hole size of 8-3/4 and casing size of 4-1/2. Production casing will continue to run from 7127'-10291' with a hole size of 7-7/8 and casing size of 4-1/2.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Bonnie Lamond

Title: Permitting Technician Date: _____ Email: bonnie.lamond@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

| |
|-------------------|
| API NUMBER |
| 05 |

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTC' located at: W:\Inetpub\NetReports\policy_ntc.rdl. Please check th

Attachment Check List

| Att Doc Num | Name |
|-------------|------------------------|
| 400374590 | WELL LOCATION PLAT |
| 400374592 | DEVIATED DRILLING PLAN |
| 400374593 | DIRECTIONAL DATA |
| 400375674 | FED. DRILLING PERMIT |

Total Attach: 4 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|-------------------|----------------|---------------------|
| | | |

Total: 0 comment(s)

BMP

| <u>Type</u> | <u>Comment</u> |
|---------------------|--|
| Pre-Construction | Wattles, Silt Fence, Vegetation Buffers, Slash, Topsoil Windrows (diversions & ROP's), Scheduling, Phased Construction |
| Wildlife | <p>Minimize the number, length and footprint of oil & gas development roads Use existing routes where possible Combine utility infrastructure planning (gas, electric & water) when possible with roadway planning to avoid separate utility corridors Coordinate Employee transport when possible</p> <p>Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors. Maximize use of state-of-the-art drilling technology (e.g., high efficiency rigs, coiled-tubing unit rigs, closed-loop or pitless drilling, etc.) to minimize disturbance.</p> <p>Reclaim mule deer and elk habitats with native shrubs, grasses, and forbs appropriate to the ecological site disturbed.</p> |
| Construction | <p>(Not all are used all the time) Terminal Containment, Diversions, Run-On Protection, Tracking, Benching, Terracing, ECM (Erosion Control Mulch), ECB (Erosion Control Blanket), Check Dams, Seeding, Mulching, Water Bars, Stabilized Unpaved Surfaces (Gravel), Stormwater & Snow Storage Containment, Scheduling, Phased Construction, Temporary Flumes, Culverts with inlet & outlet protection, Rip Rap, TRM (Turf Reinforcement Mats), Maintenance, Scheduling, Phased Construction, Fueling BMP's, Waste Management BMP's, Materials Handling BMP's</p> |
| Interim Reclamation | <p>Maintenance Revegetation Monitoring BMP maintenance & monitoring Weed Management</p> |

Total: 4 comment(s)