

Esenjay Operating, Inc.

Present Wellbore Configuration

Jones 2-12-4-60

Well

Morgan County

January 17 2013

Date

☐ Present Completion

☒ Plugged after production

☐ Suggested Completion

Well Bore Data

10 sacks cement at surface
Cap welded on casing

12-1/4" hole;
8-5/8" 24.00# K-55 STC Casing @ 534'
460 sacks of cement
Top of cement @ surface

7-7/8 hole

Total Depth:
6316' TVD
7040' MD

Data On This Completion

GL: 4381'
KB: 16'

50 sx Clas G Neat cement (15.8 ppg)
from 402' to 567'

Hole filled with 9 ppg mud

Nobrara Plug
50 sx Class G Neat cement (15.8 ppg)
from 5896' to 6066'

D Sand Plug
50 sx Class G Neat cement (15.8 ppg)
from 6683'-6853'

