

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400366434

Date Received:

01/08/2013

PluggingBond SuretyID

20120081

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☒

Sidetrack ☐

3. Name of Operator: PICEANCE ENERGY LLC

4. COGCC Operator Number: 10433

5. Address: 1512 LARIMER STREET #1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Julie Webb Phone: (303)339-4400 Fax: (303)399-4399

Email: jwebb@progressivepcs.net

7. Well Name: Vega Well Number: 4-144

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 8965

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 4 Twp: 10S Rng: 93W Meridian: 6

Latitude: 39.217964 Longitude: -107.777764

Footage at Surface: 2300 feet FNL/FSL 1631 feet FEL/FWL
FSL FWL

11. Field Name: Vega Field Number: 85930

12. Ground Elevation: 8030 13. County: MESA

14. GPS Data:

Date of Measurement: 07/02/2008 PDOP Reading: 6.0 Instrument Operator's Name: T. Viers/ Bookcliff

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
715 FSL 330 FWL 715 FSL 330 FWL
Sec: 4 Twp: 10S Rng: 93W Sec: 4 Twp: 10S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 311 ft

18. Distance to nearest property line: 291 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 360 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	399-4		
Williams Fork	WMFK	399-4		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T10S R93W - SEC 4: W2/SW; SEC 15: NW/NE. Piceance is surf. owner.

25. Distance to Nearest Mineral Lease Line: 330 ft

26. Total Acres in Lease: 120

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Reclaim water & bury cutting

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	55	0	60	200	60	0
SURF	12+1/4	8+5/8	32	0	2,200	740	2,200	0
1ST	7+7/8	4+1/2	11.6	0	8,965	477	8,965	5,447

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that all conditions in the original permit are the same. There have been no changes to land use, well construction or the lease. This pad is built. No expansion or additional disturbance will occur. Closed loop system will be used. PICEANCE LLC IS THE SURFACE OWNER. This Refile Form 2 does not require a Form 2A because the pad has been constructed, a closed loop system is being used so no pits need to be constructed, the refilled well will not require any expansion / additional surface disturbance of the pad. The location is not in a wildlife restricted surface occupancy area (RSO); consultation with CDOW is not required and the location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).; consultation with CDPHE is not required.

34. Location ID: 334442

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julie Webb

Title: Regulatory Analyst Date: 1/8/2013 Email: jwebb@progressivepcs.net

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 1/31/2013

API NUMBER

05 077 09818 00

Permit Number: _____ Expiration Date: 1/30/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

Applicable Policies and Notices to Operators

NW Colorado Notification Policy.

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
400366434	FORM 2 SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Location built w/ 3 PR's. No LGD or public comments. Final Review--passed.	1/30/2013 8:06:50 AM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 220 FEET DEEP.	1/14/2013 10:47:37 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)