

## Upr 42 Pan Am "AS" #1 WBD (P&A)

Surface Casing - 8 5/8" 24# set @ 211' (Capacity = 0.0636 bbl/ft & 0.3575 ft <sup>3</sup> /ft)		
Production Casing - 4.5" 11.6# set @ 8395' (Capacity = 0.0155 bbl/ft & 0.0895 ft <sup>3</sup> /ft)		
Production Open Hole - 7 7/8" hole to 8395' (Capacity = 0.0602 bbl/ft & 0.3381 ft <sup>3</sup> /ft)		
Tubing String - 2 3/8" (Capacity 0.00387 bbl/ft & 0.02171 ft <sup>3</sup> /ft)		
cement w/ CBL	Assumed cement w/ no CBL	New Proposed Cement

