

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400377265

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

3. Name of Operator: WPX ENERGY RYAN GULCH LLC

4. COGCC Operator Number: 10286

5. Address: 1001 17TH STREET #1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Howard Harris Phone: (303)606-4086 Fax: (303)629-8268

Email: howard.harris@wpxenergy.com

7. Well Name: federal Well Number: RGU 431-27-198

8. Unit Name (if appl): Ryan Gulch Unit Unit Number: COC068269

9. Proposed Total Measured Depth: 12277

WELL LOCATION INFORMATION

10. QtrQtr: Lot 6 Sec: 27 Twp: 1S Rng: 98W Meridian: 6

Latitude: 39.936229 Longitude: -108.379909

Footage at Surface: 2070 feet FNL/FSL 2151 feet FEL/FWL
FNL FWL

11. Field Name: Sulphur Creek Field Number: 80090

12. Ground Elevation: 6560 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 12/18/2012 PDOP Reading: 2.1 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
1043 FNL 1831 FEL 1043 FNL 1831 FEL
Sec: 27 Twp: 1S Rng: 98W Sec: 27 Twp: 1S Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5520 ft

18. Distance to nearest property line: 5860 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 601 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
Sego	SEGO			
Williams Fork	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC50701

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See Attached

25. Distance to Nearest Mineral Lease Line: 1631 ft 26. Total Acres in Lease: 1409

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use, Evap & Backfill

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	18	48	0	80	50	80	0
SURF	14+3/4	9+5/8	36	0	3,670	1,363	3,670	0
1ST	8+3/4	4+1/2	11.6	0	12,277	843	12,277	7,362

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Top of cement for production casing will be approx 200 feet above the top of Mesaverde. Closed mud system will be used. Federal minerals and surface. The wells will be drilled from the existing RGU 22-27-198 pad which presently has three producing wells on it. The existing pad will be expanded to accommodate the proposed four additional wells. An associated form 2A is being submitted for the pad expansion.

34. Location ID: 335926

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: _____ Email: howard.harris@wpenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_MTO' located at: W:\data\pub\Nat\Report\policy_mto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400377714	DIRECTIONAL DATA
400377717	DEVIATED DRILLING PLAN
400377721	FED. DRILLING PERMIT
400377722	WELL LOCATION PLAT
400377723	LEGAL/LEASE DESCRIPTION

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)