



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600549

Date	7-19-12	Well Owner	Kerr McGee	Well No.	37-3H2	Lease	CANON
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	810		
Surface	9 5/8" CSG-36# 13 1/4" HOSE	Bottom of Surface		FL	803		
Plug		Plug Landed @	758	FL	Time On	0700	
Production		Pipe Landed @	803	FL	Plug Down	0930	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	600	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Fio-Cete 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	0835	0840	
Disp. Rate 5 BPM	Mixing	0840	0915	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	0915	0918	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0918	0930	
Water/Cement 6.25 Gal/SK				
Water Temp. 74°F				
Total Slurry Vol. 141.0	BBLS Cement			
Landed Plug @ 800	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 20	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 58.6	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			2012093
1219/1217		Bulk Truck		44/44			

80012090

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH Z., ERNIE, JOSH A.

Received By Randy Case
Customer or His Agent