



State  
of  
Colorado

Kubeczko - DNR, Dave <dave.kubeczko@state.co.us>

## WPX Energy Rocky Mountain LLC, Federal DOE 1-W-27 Pad, Lot 6 Sec 27 T6S R95W, Garfield County, Form 2A (#400350508) Review

Kubeczko - DNR, Dave <dave.kubeczko@state.co.us>

Thu, Feb 7, 2013 at 4:00 PM

To: Dave Kubeczko - DNR <dave.kubeczko@state.co.us>

Scan No 2106511

CORRESPONDENCE

2A#400350508

----- Forwarded message -----

From: Kubeczko - DNR, Dave <dave.kubeczko@state.co.us>

Date: Thu, Feb 7, 2013 at 3:58 PM

Subject: WPX Energy Rocky Mountain LLC, Federal DOE 1-W-27 Pad, Lot 6 Sec 27 T6S R95W, Garfield County, Form 2A (#400350508) Review

To: [howard.harris@wpxenergy.com](mailto:howard.harris@wpxenergy.com)

Howard,

I have been reviewing the Federal DOE 1-W-27 Pad **Form 2A** (#400350508). COGCC will attach the following conditions of approval (COAs) based on the information WPX has submitted on or attached to the Form 2A prior to passing the Oil and Gas Location Assessment (OGLA) review.

**General:** The following conditions of approval (COAs) will apply:

**COA 91** - Notify the COGCC 48 hours prior to start of pad construction, rig mobilization, spud, and start of hydraulic stimulation operations using Form 42 (the appropriate COGCC individuals will automatically be email notified, including the LGD for hydraulic stimulation operations).

**COA 5** - Operator must implement best management practices to contain any unintentional release of fluids, including any fluids conveyed via temporary surface pipelines or buried permanent pipelines.

**COA 23** - Operator must ensure secondary containment for any volume of fluids contained at well site during drilling and completion operations; including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures (i.e., best management practices (BMPs) associated with stormwater management) sufficiently protective of nearby surface water. Any berm constructed at the well pad location will be stabilized, inspected at regular intervals (at least every 14 days), and maintained in good condition.

**COA 38** - The moisture content of any cuttings in a cuttings pit, trench, or pile shall be as low as practicable to prevent accumulation of liquids greater than de minimis amounts. At the time of closure, if the drill cuttings are to be left onsite, they must also meet the applicable standards of table 910-1.

**COA 25** - Flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline, storage vessel, or lined pit (only if an amended Form 2A has been submitted/approved and a Form 15 Earthen Pit Permitted has been submitted/approved) located on the well pad; or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area with additional downgradient perimeter berming. The area where flowback fluids will be stored/reused must be constructed to be sufficiently impervious to contain any spilled or released

material.

**COA 58** - Berms or other containment devices shall be constructed to be sufficiently impervious (preferably corrugated steel with poly liner) to contain any spilled or released material around crude oil, condensate, and produced water storage tanks.

Based on the information provided in the Form 2A by WPX, COGCC will attach these COAs to the Form 2A permit; WPX does not need to respond, unless you have questions or concerns with details in this email. If you have any questions regarding this email, please do not hesitate to call me at (970) 309-2514 (cell), or email. Thanks.

Dave

**David A. Kubeczko, PG**  
**Oil and Gas Location Assessment Specialist**

Colorado Oil & Gas Conservation Commission  
Northwest Area Office  
796 Megan Avenue, Suite 201  
Rifle, CO 81650  
FAX: (970) 625-5682  
Cell: (970) 309-2514  
[dave.kubeczko@state.co.us](mailto:dave.kubeczko@state.co.us)



*Please consider the environment before printing this e-mail*

--

Dave

**David A. Kubeczko, PG**  
**Oil and Gas Location Assessment Specialist**

Colorado Oil & Gas Conservation Commission  
Northwest Area Office  
796 Megan Avenue, Suite 201  
Rifle, CO 81650  
FAX: (970) 625-5682  
Cell: (970) 309-2514  
[dave.kubeczko@state.co.us](mailto:dave.kubeczko@state.co.us)



*Please consider the environment before printing this e-mail*