

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400374971

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: MARI CLARK Phone: (303)228-4413 Fax: (303)228-4286

Email: mclark@nobleenergyinc.com

7. Well Name: COOK STATE LD Well Number: 36-78HN

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 9860

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 36 Twp: 9N Rng: 58W Meridian: 6

Latitude: 40.714420 Longitude: -103.818970

Footage at Surface: 250 feet FNL/FSL FNL 660 feet FEL/FWL FWL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 4744 13. County: WELD

14. GPS Data:

Date of Measurement: 10/10/2012 PDOP Reading: 1.2 Instrument Operator's Name: ALAN HNIZDO

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
724 FNL 670 FWL 660 FSL 660 FWL
Sec: 36 Twp: 9N Rng: 58W Sec: 36 Twp: 9N Rng: 58W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 4596 ft

18. Distance to nearest property line: 250 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 2338 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	UNSPACED	640	SEC. 36: ALL

21. Mineral Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian Lease #: 93/1173-5

22. Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T9N, R58W, Sec. 36: ALL

25. Distance to Nearest Mineral Lease Line: 660 ft

26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16+0/0		0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	550	270	550	0
1ST	8+3/4	7+0/0	26	0	5,981	410	5,981	
1ST LINER	6+1/8	4+1/2	11.6	5831	9,860			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments THERE ARE NO OTHER WELLS IN THIS SECTION PERMITTED/COMPLETED IN SAME FORMATION. NEAREST WELL IN NIOBRARA IS FISCUS MESA 23-25H 2338' NE OF SITE. 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. THE PRODUCTION LINER WILL BE HUNG OFF INSIDE 7" CASING. PRODUCTION FACILITIES WILL BE LOCATED ON THE SAME LOCATION AND DEDICATED TO THE WELL LOCATION BEING PERMITTED.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MARI CLARK

Title: REGULATORY ANALYST II Date: _____ Email: mclark@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy NTO' located at: W:\Instrub\Net\Reports\policy_nto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400378051	DIRECTIONAL DATA
400378984	30 DAY NOTICE LETTER
400378985	DEVIATED DRILLING PLAN
400378986	WELL LOCATION PLAT

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.

Total: 3 comment(s)