

FORM
5

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400347981

Date Received:

11/29/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 10261
2. Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION
3. Address: 730 17TH ST STE 610
City: DENVER State: CO Zip: 80202
4. Contact Name: JONATHAN RUNGE
Phone: (970) 669-7411
Fax: (970) 669-407

5. API Number 05-123-35730-00
6. County: WELD
7. Well Name: BALDRIDGE Well Number: 17-1
8. Location: QtrQtr: SWSE Section: 36 Township: 7N Range: 67W Meridian: 6
Footage at surface: Distance: 243 feet Direction: FSL Distance: 2184 feet Direction: FEL
As Drilled Latitude: 40.524091 As Drilled Longitude: -104.840061

GPS Data:

Date of Measurement: 10/25/2012 PDOP Reading: 1.9 GPS Instrument Operator's Name: Owen McKee

** If directional footage at Top of Prod. Zone Dist.: 1348 feet. Direction: FNL Dist.: 1343 feet. Direction: FEL

Sec: 1 Twp: 6N Rng: 67W

** If directional footage at Bottom Hole Dist.: 1366 feet. Direction: FNL Dist.: 1345 feet. Direction: FEL

Sec: 1 Twp: 6N Rng: 67W

9. Field Name: EATON 10. Field Number: 19350

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 09/09/2012 13. Date TD: 09/14/2012 14. Date Casing Set or D&A: 09/15/2012

15. Well Classification:

Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 7775 TVD** 7459 17 Plug Back Total Depth MD 7749 TVD** 7433

18. Elevations GR 4876 KB 4892

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Density, Neutron, Induction, CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	606	277	0	606	VISU
1ST	7+7/8	4+1/2	11.6	0	7,762	915	1,470	7,762	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,840		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,425		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,060		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,361		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,587		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,610		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jonathan Runge

Title: Consultant Date: 11/29/2012 Email: jrunge@petersonenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400348550	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400348077	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400347981	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400347985	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400348078	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400352028	LAS-TRIPLE COMBINATION	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)