



State  
of  
Colorado

Krabacher - DNR, Jay <jay.krabacher@state.co.us>

## rig 24s daily report 1-26-13

1 message

Darie Roehm <darieroehm@yahoo.com>

Mon, Feb 4, 2013 at 7:25 PM

Reply-To: Darie Roehm <darieroehm@yahoo.com>

To: Jay Krabracher <jay.krabacher@state.co.us>, Jay Krabracher <nusratkhan@aol.com>, Chad Vannest <chadvannest@hotmail.com>

# MAGNA ENERGY SERVICE RIG 24

DATE	LOCATION
1-26-13	Eldon Gerber 07-24

## SUMMARY

6:00-Crew travel-JSA meeting  
 7:00-RIH with 5 ½" CICR on bottom of tbg  
 7:40-Set CICR @655' (20 jts)  
 8:00-Start pumping 15.8# cement (1 bbl FW ahead-32 sacks/6.4 bbls cmt-1 bbl FW behind-.4 bbl disp. {leaving 27 sacks/5.4 bbls below CICR & behind Csg}-sting out-1.6 bbl disp. {leaving 5 sacks/1 bbl on top CICR})  
 8:30-Lay down all tbg on float-Rd floor-Nd BOP  
 9:30-Rig down-move equipment away from well  
 10:20-Dig out around well-drop Csg & cut wellhead off  
 12:10-Pump surface plug (12 sacks/2.4 bbls cmt-50' to surface, inside & out)  
 1:00-Load equipment-back fill well-prep equipment for move  
 5:30-Crew travel  
 6:00

NAMES	HOURS	SUBSISTANCE
Darie Roehm	12	Yes
Tommy Obrian	12	Yes
Berry Knoke	12	Yes
Jason Grassord	12	Yes
Ty Hurt	12	yes

## NOTES

Head west out of Craig on Hwy 40 2.5 miles-turn right onto CR 64 for 3.5 miles-  
turn left onto CR 76 for 1.5 miles all the way to the rig

PO#s	COST
#45699/Best Western/Rooms/\$490.45 #45700/O'Reilly Auto Parts/Light, Sealed Beam, Butt Splice/\$19.25	