

# MAGNA ENERGY SERVICE RIG 24

DATE	LOCATION
1-25-13	Eldon Gerber 07-24

## SUMMARY

6:00-Crew travel-JSA meeting  
 7:00-RIH to 4775' (152 jts)-Ru cement equip.-wait for water  
 9:15-Start pumping 15.8# Cmt (1 bbl FW ahead-15 sacks/3 bbls cmt-1 bbl FW behind-17 bbls disp.)(Cmt 4775 to 4640')  
 10:00-Lay down 6 jts-reverse circ. tbg clean (20 bbls)  
 10:20-Pressure test well to 500 psi for 15 mins (20 psi +/- loss)  
 10:35-Bleed psi off-lay down 40 jts-POOH 53 stands  
 11:50-Ru wireline-RIH & do a CBL from 4550' to 681' (determined good cement past 3392')  
 2:50-RIH with perforated sub on bottom of tbg-tag CIBP @ (  
 3:30-Start pumping 15.8# Cmt (1 bbl FW ahead-5 sacks/1 bbl cmt-1 bbl FW behind-13 bbl disp.)(TOC @3300')  
 3:50-Pull 10 stands-lay down 87 jts  
 4:55-Ru wireline-RIH with perf gun & shoot 4 holes @761'-get an injection rate of 2 bbls a min. @800 psi-Rd wireline  
 5:30-Shut well in-drain equipment-secure rig & location  
 6:30-Crew travel  
 7:30

NAMES	HOURS	SUBSISTANCE
Darie Roehm	13.5	Yes
Tommy Obrian	13.5	Yes
Berry Knoke	13.5	Yes
Jason Grassord	13.5	Yes
Ty Hurt	13.5	yes

## NOTES

Head west out of Craig on Hwy 40 2.5 miles-turn right onto CR 64 for 3.5 miles-

turn left onto CR 76 for 1.5 miles all the way to the rig

REVINUE	COST
#45696/Best Western/Rooms/\$490.45 #45697/B & B Welders Supply/Propane/\$88.98 #45698/Napa/Hydro Hose-Swivel-Multi meter/\$104.01	\$517.17