

## Weld County, Colorado, Northern Part

### 32—Kim-Mitchell complex, 6 to 9 percent slopes

#### Map Unit Setting

*Elevation:* 3,500 to 6,500 feet  
*Mean annual precipitation:* 11 to 17 inches  
*Mean annual air temperature:* 46 to 54 degrees F  
*Frost-free period:* 120 to 160 days

#### Map Unit Composition

*Kim and similar soils:* 45 percent  
*Mitchell and similar soils:* 35 percent  
*Minor components:* 20 percent

#### Description of Kim

##### Setting

*Landform:* Fans, alluvial fans, plains  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Calcareous loamy alluvium and/or colluvium

##### Properties and qualities

*Slope:* 6 to 9 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Well drained  
*Capacity of the most limiting layer to transmit water*  
*(Ksat):* Moderately high (0.20 to 0.60 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Calcium carbonate, maximum content:* 15 percent  
*Maximum salinity:* Nonsaline to very slightly saline (0.0 to 4.0 mmhos/  
cm)  
*Available water capacity:* High (about 9.7 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 6e  
*Land capability (nonirrigated):* 6e  
*Ecological site:* Loamy Plains (R067BY002CO)

##### Typical profile

*0 to 3 inches:* Loam  
*3 to 7 inches:* Clay loam  
*7 to 60 inches:* Loam

#### Description of Mitchell

##### Setting

*Landform:* Alluvial fans, fans, plains  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Calcareous loamy alluvium

### **Properties and qualities**

*Slope:* 6 to 9 percent

*Depth to restrictive feature:* More than 80 inches

*Drainage class:* Well drained

*Capacity of the most limiting layer to transmit water*

*(Ksat):* Moderately high to high (0.57 to 5.95 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Calcium carbonate, maximum content:* 15 percent

*Available water capacity:* High (about 10.8 inches)

### **Interpretive groups**

*Land capability classification (irrigated):* 6e

*Land capability (nonirrigated):* 6e

*Ecological site:* Siltstone Plains (R067BY009CO)

### **Typical profile**

*0 to 7 inches:* Silt loam

*7 to 60 inches:* Silt loam

### **Minor Components**

#### **Keota**

*Percent of map unit:* 7 percent

#### **Thedalund**

*Percent of map unit:* 7 percent

#### **Haverson**

*Percent of map unit:* 6 percent

## **Data Source Information**

Soil Survey Area: Weld County, Colorado, Northern Part

Survey Area Data: Version 8, Apr 30, 2009