



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600560

Date	07-11-12	Well Owner	Kerr McGee	Well No.	14N-W3H2	Lease	CANNON
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	805		
Surface	9 5/8" CSG-36# 13 1/2" NOLA	Bottom of Surface		Fl.	800		
Plug		Plug Landed @	757	Fl.	1500		
Production		Pipe Landed @	800	Fl.	1915		

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	600	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge 2073148	126	Miles		
Fuel Surcharge 800/2090	126	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	1827	1834		
Disp. Rate 5 BPM	1834	1900		
Slurry Vol. 1.32 ³ Cu.Ft./Sk	1900	1903		
Slurry Wt. 14.8 - 15.0 PPG	1903	1915		
Water/Cement 6.25 Gal/SK				
Water Temp. 75°F				
Total Slurry Vol. 141		BBLS Cement		
Landed Plug @ 775		PSI/Final Lift @ 400	PSI	
Pre-Flush W/ 30		BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/ 58.5		BBLS H ₂ O	State CO 2.9%	Tax
Circulate 6		BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		42			
1214-1217		Bulk Truck		42-42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By SIM, EVAN, STEVE, MARCOS

Received By Randy Case
Customer or His Agent