

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400372631

Date Received:

01/21/2013

PluggingBond SuretyID

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JENNIFER LIND Phone: (720)876-5890 Fax: (720)876-6890

Email: JENNIFER.LIND@ENCANA.COM

7. Well Name: SG Well Number: 8515A-27 L27496

8. Unit Name (if appl): BIG JIMMY UNIT Unit Number: COC74105X

9. Proposed Total Measured Depth: 12970

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 27 Twp: 4S Rng: 96W Meridian: 6

Latitude: 39.671103 Longitude: -108.160242

Footage at Surface: 1836 feet FNL/FSL FSL 1095 feet FEL/FWL FWL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 8106 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 07/31/2012 PDOP Reading: 1.5 Instrument Operator's Name: ROBERT KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1091 FSL 1458 FEL FEL Bottom Hole: FNL/FSL 1091 FSL 1458 FEL FEL
Sec: 27 Twp: 4S Rng: 96W Sec: 27 Twp: 4S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 16281 ft

18. Distance to nearest property line: 3734 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 264 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-13		

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC61137

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

PLEASE SEE ATTACHED MAP

25. Distance to Nearest Mineral Lease Line: 1091 ft

26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RECYCLE AND BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	LINE PIPE	0	120	176	120	0
SURF	12+1/4	9+5/8	36	0	2,500	782	2,500	0
1ST	7+7/8	4+1/2	11.6	0	12,970	1,389	12,970	7,162

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments PLEASE NOTE THAT ENCANA OIL & GAS (USA) INC. IS THE SURFACE OWNER FOR THIS LOCATION. #17 IS CALCULATED FROM NEAREST BUILDING. SURFACE CASING HOLE SIZE WILL BE 14-3/4", 12-1/4" OR 13-1/2". CONDUCTOR CASING WILL BE CEMENTED TO SURFACE.

34. Location ID: 335939

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JENNIFER LIND

Title: REGULATORY ANALYST

Date: 1/21/2013

Email: JENNIFER.LIND@ENCANA.C

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 2/12/2013

API NUMBER

05 045 21895 00

Permit Number: _____

Expiration Date: 2/11/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS IS REQUIRED.

Applicable Policies and Notices to Operators

Piceance Rulison Field - Notice to Operators.

NW Colorado Notification Policy.

Attachment Check List

Att Doc Num	Name
400372631	FORM 2 SUBMITTED
400372642	TOPO MAP
400372646	MINERAL LEASE MAP
400372647	DEVIATED DRILLING PLAN
400372648	WELL LOCATION PLAT
400372649	FED. DRILLING PERMIT
400372650	DIRECTIONAL DATA

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Added spacing order #. OK upon 2A approval. Approved 2/7/13.	1/31/2013 10:43:34 AM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.	1/29/2013 7:26:35 PM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)