

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400378484

Date Received:

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER ☐ Pilot ☐  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

PluggingBond SuretyID

20100227

3. Name of Operator: CONOCO PHILLIPS COMPANY

4. COGCC Operator Number: 19160

5. Address: P O BOX 2197

City: HOUSTON State: TX Zip: 77252-2197

6. Contact Name: Justin Carlile Phone: (432)6889165 Fax: (432)6886019

Email: justin.carlile@conocophillips.com

7. Well Name: Tebo 33 Well Number: 1H

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 8230

## WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 33 Twp: 4S Rng: 64W Meridian: 6

Latitude: 39.654664 Longitude: -104.564814

Footage at Surface: 900 feet FNL/FSL 310 feet FEL/FWL  
 FSL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5839.5 13. County: ARAPAHOE

## 14. GPS Data:

Date of Measurement: 10/08/2012 PDOP Reading: 2.0 Instrument Operator's Name: Robert Kay

15. If well is ☐ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2300 ft

18. Distance to nearest property line: 310 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1709 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	State	640	SWSW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: 22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Township 4 South, Range 64 West, 6th P.M. Section 33: ALL

25. Distance to Nearest Mineral Lease Line: 310

26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24+0/0	16+0/0	39.7	0	100	50	100	0
SURF	12+1/4	9+5/8	36	0	2,165	640	2,165	0
OPEN HOLE	0+0/0	0+0/0	0	2165	8,230			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Cuttings will be taken by certified transport company, and disposed of at a certified disposal facility.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Justin Carlile

Title: Regulatory Specialist Date: \_\_\_\_\_ Email: justin.carlile@conocophillips.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy\_NTO' located at: W:\natpub\Nat\Reports\policy\_nto.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400379983	WELL LOCATION PLAT

Total Attach: 1 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Site Specific	<p>ConocoPhillips Groundwater Monitoring Program</p> <p>ConocoPhillips has adopted the Colorado Oil and Gas Association (COGA) voluntary groundwater testing program to establish baseline groundwater quality conditions around new oil well locations in their leased area. The sampling program will allow the company (ConocoPhillips) to evaluate the groundwater conditions before drilling a well and also to monitor water quality afterward.</p> <p>The program will be in accordance with the guidance set forth in the Voluntary Baseline Groundwater Quality Sampling Program last updated on November 15, 2011. Under the sampling protocol, water samples would be collected from the two closest groundwater sources with reasonable access. The sample points, permitted or registered wells, would be located within ½ mile of the proposed well surface location.</p> <p>Sampling will be conducted based on the landowner granting access to the well location and agreeing to have the laboratory analytical results submitted to COGCC for posting to a database viewable by the public.</p> <p>Samples will be analyzed for the constituents listed in Table 1 of the Groundwater Sampling and Analytical Program.</p>

Total: 1 comment(s)