

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400380912

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER Horizontal  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☒

Sidetrack ☐

PluggingBond SuretyID

20100108

3. Name of Operator: CARRIZO OIL & GAS INC

4. COGCC Operator Number: 10338

5. Address: 500 DALLAS STREET #2300

City: HOUSTON State: TX Zip: 77002

6. Contact Name: Tina Taylor Phone: (713)328-1000 Fax: (713)328-1060

Email: tina.taylor@crzo.net

7. Well Name: Shutt Well Number: 1-25-11-62

8. Unit Name (if appl):  Unit Number:

9. Proposed Total Measured Depth: 11144

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 25 Twp: 11N Rng: 62W Meridian: 6

Latitude: 40.899750 Longitude: -104.273400

Footage at Surface: 242 feet FNL/FSL 1294 feet FEL/FWL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5130 13. County: WELD

14. GPS Data:

Date of Measurement: 10/25/2012 PDOP Reading: 1.8 Instrument Operator's Name: Marc Woodard

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 650 FNL 650 FEL/FWL 650 FSL 650 FWL 650 FWL  
Sec: 25 Twp: 11N Rng: 62W Sec: 25 Twp: 11N Rng: 62W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 240 ft

18. Distance to nearest property line: 242 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 650 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	421-3	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20100170

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T11N R62W, 6th P.M. Section 25:SW

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
1ST	8+3/4	7	23	1400	7,038	679	7,038	1,400
1ST LINER	6+1/4	4+1/2	11.6	6350	11,144			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Carrizo is refiling Shutt 1-25-11-62 for the horizontal 01 completion. Carrizo has filed a sundry for the Pilot well completion 00. No conductor will be set. Swell packer will be set across 600' from section line to keep wellbore from 7" casing shoe to swell packer unproduced.

34. Location ID: 425417

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Tina Taylor

Title: Regulatory Compliance Date: \_\_\_\_\_ Email: tina.taylor@crzo.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

#### API NUMBER

05 123 34382 00

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy\_MTO' located at: W:\Inetpub\Net\Report\policy\_etc.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400380915	WELL LOCATION PLAT
400380916	DEVIATED DRILLING PLAN
400380921	DIRECTIONAL DATA

Total Attach: 3 Files

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

### BMP

Type	Comment
Material Handling and Spill Prevention	Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids. Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit/Pond.
Storm Water/Erosion Control	Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.
Site Specific	Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use. Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source. Operator will participate in the Colorado Oil & Gas Association Voluntary Baseline Groundwater Quality Sampling Program. Operator will implement interim reclamation measures immediately after construction of the location to stabilize cut and fill slopes, stabilize the topsoil and spoil stockpiles, establish desirable vegetation and control weeds on the location.
Construction	The location will be fenced and the fenced area will include the Fresh Water Storage Pit.
Pre-Construction	The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.
Planning	A Form 15 Pit Report will be submitted within 30 days of construction of the fresh water storage pit.

Total: 6 comment(s)