

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400366460

Date Received:

01/08/2013

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☒

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Erin Hochstetler Phone: (720)876-5827 Fax: ()

Email: erin.hochstetler@encana.com

7. Well Name: Rasmussen Well Number: 11-28

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8406

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 28 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.111500 Longitude: -105.011380

Footage at Surface: 1962 feet FNL 1770 feet FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4935 13. County: WELD

14. GPS Data:

Date of Measurement: 06/02/2010 PDOP Reading: 2.0 Instrument Operator's Name: BURKE

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
510 FNL 800 FWL 510 FNL 800 FWL  
Sec: 28 Twp: 2N Rng: 68W Sec: 28 Twp: 2N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 639 ft

18. Distance to nearest property line: 446 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 760 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| CODELL                 | CODL           | 407                     | 320                           | N/2                                  |
| J SAND                 | JSND           | 232-23                  | 320                           | N/2                                  |
| NIOBRARA               | NBRR           | 407                     | 320                           | N/2                                  |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

E2NW4NW4, E2NW4, NW4NE4 SEC 28-2N-68W

25. Distance to Nearest Mineral Lease Line: 510 ft

26. Total Acres in Lease: 140

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft      | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|------------|---------------|---------------|-----------|---------|---------|
| SURF        | 12+1/4       | 8+5/8          | 24         | 0             | 800           | 350       | 800     | 0       |
| 1ST         | 7+7/8        | 4+1/2          | 11.6       | 0             | 8,406         | 260       | 8,406   | 7,411   |
|             |              |                | Stage Tool |               | 5,113         | 150       | 5,113   | 4,107   |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. Encana Oil & Gas (USA) Inc. requests approval of Rule 318Aa exception location: Wellhead is to be located outside of a GWA drilling window. Waivers are attached. There have been no changes to the location.

34. Location ID: 333145

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Erin Hochstetler

Title: Permitting Technician Date: 1/8/2013 Email: erin.hochstetler@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 2/13/2013

#### API NUMBER

05 123 32894 00

Permit Number: \_\_\_\_\_ Expiration Date: 2/12/2015

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well testing requirements per Rule 318A.

- 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU..
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Applicable Policies and Notices to Operators**

Notice Concerning Operating Requirements for Wildlife Protection.

### **Attachment Check List**

| Att Doc Num | Name                   |
|-------------|------------------------|
| 400366460   | FORM 2 SUBMITTED       |
| 400366587   | 30 DAY NOTICE LETTER   |
| 400366588   | EXCEPTION LOC REQUEST  |
| 400366589   | EXCEPTION LOC WAIVERS  |
| 400366592   | DEVIATED DRILLING PLAN |
| 400366594   | WELL LOCATION PLAT     |
| 400366595   | MINERAL LEASE MAP      |
| 400366596   | DIRECTIONAL DATA       |

Total Attach: 8 Files

### **General Comments**

| <b><u>User Group</u></b> | <b><u>Comment</u></b>   | <b><u>Comment Date</u></b> |
|--------------------------|---|----------------------------|
| Permit                   | Final Review Completed. No LGD or public comment received.  | 2/12/2013<br>4:27:19 PM    |
| Permit                   | ON HOLD: w/o Engineering's request. ok to pass.   | 2/4/2013 9:08:24<br>AM     |
| Permit                   | Changed Unit config from GWA to N/2 per spacing orders. Added the comment "There have been no changes to the location." ok to pass.                     | 1/16/2013<br>1:49:48 PM    |
| Permit                   | Operator requests approval of a Rule 318Aa exception location: Wellhead is to be located outside of a GWA drilling window. Request and Waiver attached. | 1/16/2013<br>1:49:47 PM    |

Total: 4 comment(s)

### **BMP**

| <b><u>Type</u></b> | <b><u>Comment</u></b> |
|--------------------|-----------------------|
|                    |                       |

Total: 0 comment(s)