

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400349575

Date Received:

01/16/2013

PluggingBond SuretyID

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: JAN KAJIWARA Phone: (303)228-4092 Fax: (303)228-4286

Email: jkajiwara@nobleenergyinc.com

7. Well Name: SHABLE FEDERAL LB Well Number: 33-78HN

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 10607

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 33 Twp: 9N Rng: 60W Meridian: 6

Latitude: 40.712408 Longitude: -104.105867

Footage at Surface: 288 feet FNL/FSL 400 feet FEL/FWL
FNL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4940 13. County: WELD

14. GPS Data:

Date of Measurement: 06/01/2012 PDOP Reading: 2.1 Instrument Operator's Name: Dave Swanson

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
729 FNL 662 FWL 660 FSL 660 FWL
Sec: 33 Twp: 9N Rng: 60W Sec: 33 Twp: 9N Rng: 60W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 281 ft

18. Distance to nearest property line: 288 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1389 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-3	640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T9N- R60W SECTION 33: W/2, SE

25. Distance to Nearest Mineral Lease Line: 660 ft

26. Total Acres in Lease: 480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16+0/0		0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	580	270	580	0
1ST	8+3/4	7+0/0	26	0	6,725	460	6,725	
1ST LINER	6+1/8	4+1/2	11.6	6575	10,607			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. THREE WELL PAD SHABLE FEDERAL LB29-62HN, FEDERAL LB33-78HN, LB32-68HN. NEAREST WELL IS SHABLE LB32-68HN AT 1389'. SUNDRIES TO ABANDON LOCATIONS FOR THE FIVE WELL DRAW 17-29H AND FIVE WELL DRAW 21-33H HAVE BEEN SUBMITTED. SUA ATTACHED FOR INFORMATION. SPACING UNIT ALSO CONTAINS FEDERAL MINERALS LEASE # COC-69957.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JAN KAJIWARA

Title: REGULATORY ANALYST

Date: 1/16/2013

Email: jkajiwara@nobleenergyinc.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 2/15/2013

API NUMBER

05 123 36799 00

Permit Number: _____

Expiration Date: 2/14/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice of spud via electronic Form 42.
- 2) Set at least 580' of surface casing. Cement to surface.
- 3) Provide cement coverage on intermediate casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
2485375	SURFACE CASING CHECK
400349575	FORM 2 SUBMITTED
400365620	30 DAY NOTICE LETTER
400365622	WELL LOCATION PLAT
400368225	DIRECTIONAL DATA
400368226	DEVIATED DRILLING PLAN
400370047	SURFACE AGRMT/SURETY

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Per operator corrected distance to nearest road. Final Review Completed. No LGD or public comment received.	2/12/2013 10:21:11 AM
Permit	Requested updated distance to nearest road.	2/12/2013 6:49:29 AM
Permit	Corrected distance to lease line and updated comments to include Fed lease number. Initial review complete.	2/4/2013 11:59:00 AM
Engineer	No existing wells within 500' of proposed directional w/o zonal isolation.	2/4/2013 8:02:16 AM
Permit	Returned to draft. Requested #19 and #22a to be answered.	1/17/2013 11:37:38 AM

Total: 5 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Material Handling and Spill Prevention	Spill prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.

Total: 3 comment(s)