



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

200641

Date 8/13/12	Well Owner PDC	Well No. 34F-212	Lease Wells Ranch
County Weld	State Colorado	Field	
Charge to Petroleum Development Corporation	Charge Code		
Address 1775 Sherman Street, Suite # 3000 (E881610 #14)			For Office Use Only
City, State Denver, Colorado 80203			
Pump Truck No. 1208	Code	Bulk Truck No. 014/1218	Code
Type of Job	Depth	Fl. 913	To
Surface 9 5/8" CG-36" 13 3/4" Hole	Bottom of Surface	Fl. 897	To
Plug	Plug Landed @ 856	Fl. Time On 11:00	
Production	Pipe Landed @ 897	Fl. Time Off Plug Done	

Reference No.	Description	Qty.	Meas.	Unit
	Pump Truck Charge			
	Cement Neat	800	SKS	
	Poz. Mix			
	Calcium Chloride	3%		
	Gel % Flo-Cele $\frac{1}{4}$ #Per Sack			
	Handling Charge ZJBS1			
	Hauling Charge AEE			
	Additional Cement Coding			
9 5/8"	Centralizers By 1	8		80°
"	Cement Basket	1		
"	Guide Shoe	1		
"	AFLU FIDAT INSERT	1		
	Box thread lock	1		
	Mix Rate 4 BPM	Slurry Vol - 1.18 FT³/BBL - water Temp - 6		
	Disp Rate 5 BPM	Slurry WT 15.2 PPG		
	Plug landed @ 1600 PSI	Total Slurry Vol - 116.1 BBL Cement		
Remarks: Pre-Flush w/ 30 BBL H₂O	Tax Reference Code	Sub Total		
Displace w/ 166.1 BBL H₂O	State CO 2.9 %	Tax		
Circulate 10 BBL Cement	Disc.	Total		

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Or
1208		Pump Truck		42		
014/1218		Bulk Truck		42/42		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to re

Delivered By **Justin Adam, Chris & Josh A**

Received By

Customer or His Agent