

FORM
2

Rev
12/05

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400378876

Date Received:

02/07/2013

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: MIRACLE PFISTER Phone: (720)876-3761 Fax: (720)876-4861

Email: miracle.pfister@encana.com

7. Well Name: IONE Well Number: 2E-2H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11412

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 2 Twp: 2N Rng: 66W Meridian: 6

Latitude: 40.173110 Longitude: -104.748730

Footage at Surface: 509 feet FNL 1410 feet FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 5046 13. County: WELD

14. GPS Data:

Date of Measurement: 07/27/2012 PDOP Reading: 1.7 Instrument Operator's Name: RICE

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 596 FNL 1821 FWL Bottom Hole: 460 FSL 1850 FWL
Sec: 2 Twp: 2N Rng: 66W Sec: 2 Twp: 2N Rng: 66W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 1477 ft

18. Distance to nearest property line: 509 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 62 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		640	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T2N-R66W Sec. 2: All; Sec 4: S/2; Sec 8: NE/4, SW/4; Sec 10: E/2, NW/4

25. Distance to Nearest Mineral Lease Line: 460 ft 26. Total Acres in Lease: 1760

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	22	16	30	0	80	80	80	0
SURF	12+1/4	9+5/8	40	0	1,053	409	1,053	0
1ST	8+3/4	7	26	0	7,409	620	7,409	0
2ND	6+1/8	4+1/2	13.5	0	11,410	233	11,410	5,300

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Unplanned sidetrack: Drilled lone 2E-2H to a total MD of 11792'. While cleaning and conditioning hole prior to 4 1/2" production casing run, the lower housing of the 5" mud motor and 6 1/8" bit separated from the bottom hole assembly. The fish is 3.7' in total length. Top of fish @ 7456' approximately. KOP of sidetrack will be 5600'. Verbal approval for the sidetrack was given by Diana Burns 2/6/2013.

34. Location ID: 430201

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MIRACLE PFISTER

Title: REGULATORY ANALYST Date: 2/7/2013 Email: miracle.pfister@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 2/22/2013

API NUMBER **05 123 36089 01** Permit Number: _____ Expiration Date: 2/21/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

For compliance:
 Comply with Rule 317.i and provide cement coverage to a minimum of 200' above the Niobrara. Verify cement coverage with a cement bond log per 317.o.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
1695530	CORRESPONDENCE
400378876	FORM 2 SUBMITTED
400378914	PLAT
400378920	DEVIATED DRILLING PLAN

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	This wellbore is an unplanned sidetrack to IONE 2E-2H (API#123-36089). Ok to pass.	2/13/2013 9:37:22 AM
Permit	This form has passed completeness.	2/8/2013 9:48:59 AM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	Operator will comply with COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
Drilling/Completion Operations	Anti-collision: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an asconstructed gyro survey will be submitted to COGCC with the Form 5.

Total: 2 comment(s)