

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400369742

Date Received:

01/14/2013

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refilling ☐Sidetrack ☐

PluggingBond SuretyID

3. Name of Operator: ENCANA OIL & GAS (USA) INC4. COGCC Operator Number: 1001855. Address: 370 17TH ST STE 1700City: DENVER State: CO Zip: 80202-56326. Contact Name: JENNIFER LIND Phone: (720)876-5890 Fax: (720)876-6890Email: JENNIFER.LIND@ENCANA.COM7. Well Name: SG Well Number: 8516A-33 E344968. Unit Name (if appl): BIG JIMMY UNIT Unit Number: COC74105X9. Proposed Total Measured Depth: 12801

## WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 34 Twp: 4S Rng: 96W Meridian: 6Latitude: 39.659700 Longitude: -108.160647

Footage at Surface: 2319 feet FNL/FSL 981 feet FEL/FWL FWL

11. Field Name: GRAND VALLEY Field Number: 3129012. Ground Elevation: 8324 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 06/01/2012 PDOP Reading: 1.3 Instrument Operator's Name: ROBERT KAY15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1197 FSL 1301 FEL 1197 FSL 1301 FEL 1197 FSL 1301 FEL 1197  
 Bottom Hole: FNL/FSL 1197 FSL 1301 FEL 1197 FSL 1301 FEL 1197  
 Sec: 33 Twp: 4S Rng: 96W Sec: 33 Twp: 4S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 3 mi18. Distance to nearest property line: 2504 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 264 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-13		

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC6555622. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

PLEASE SEE ATTACHED MAP

25. Distance to Nearest Mineral Lease Line: 1197 ft

26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RECYCLE AND BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20		0	120	176	120	0
SURF	12+1/4	9+5/8	36	0	2,500	782	2,500	0
1ST	7+7/8	4+1/2	11.6	0	12,801	1,381	12,801	7,809

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments PLEASE NOTE THAT ENCANA OIL & GAS (USA) INC. IS THE SURFACE OWNER FOR THIS LOCATION. #17 IS CALCULATED FROM NEAREST BUILDING. SURFACE CASING HOLE SIZE WILL BE 14-3/4", 12-1/4" OR 13-1/2". CONDUCTOR CASING WILL BE CEMENTED TO SURFACE.

34. Location ID: 335928

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: JENNIFER LIND

Title: REGULATORY ANALYST

Date: 1/14/2013

Email: JENNIFER.LIND@ENCANA.C

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_

Director of COGCC

Date: 2/22/2013

#### API NUMBER

05 045 21905 00

Permit Number: \_\_\_\_\_

Expiration Date: 2/21/2015

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.

(3) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

### **Applicable Policies and Notices to Operators**

Piceance Rulison Field - Notice to Operators.

NW Colorado Notification Policy.

### **Attachment Check List**

Att Doc Num	Name
400369742	FORM 2 SUBMITTED
400369750	TOPO MAP
400369754	MINERAL LEASE MAP
400369755	DEVIATED DRILLING PLAN
400369756	WELL LOCATION PLAT
400369757	FED. DRILLING PERMIT
400369758	DIRECTIONAL DATA

Total Attach: 7 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	OK, 2A #400359604 approved 2/1/13. Corrected lease line distance from 1301 to 1197.	1/25/2013 1:48:34 PM
LGD	Passed DB	1/17/2013 11:44:30 AM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 00 FEET DEEP.	1/16/2013 2:09:43 PM

Total: 3 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)