

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400380008

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☐ COALBED ☐ OTHER ☐
SINGLE ZONE ☐ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20100227

3. Name of Operator: CONOCO PHILLIPS COMPANY

4. COGCC Operator Number: 19160

5. Address: P O BOX 2197

City: HOUSTON State: TX Zip: 77252-2197

6. Contact Name: Justin Carlile Phone: (432)688-9165 Fax: (432)688-6019

Email: justin.carlile@conocophillips.com

7. Well Name: Moran Trust 2

Well Number: 1

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 8017

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 2 Twp: 5S Rng: 64W Meridian: 6

Latitude: 39.641706

Longitude: -104.516628

Footage at Surface: 1680 feet FNL/FSL FSL 1853 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5976.4 13. County: ARAPAHOE

14. GPS Data:

Date of Measurement: 01/18/2013 PDOP Reading: 1.9 Instrument Operator's Name: Robert Kay

15. If well is ☐ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 865 ft

18. Distance to nearest property line: 788 ft 19. Distance to nearest well permitted/completed in the same formation(BHL):

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-246	640	NWSE

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Township 5 South, Range 64 West, 6th P.M. Section 2: Lot 1 (81.34), S/2NE/4, SE/4

25. Distance to Nearest Mineral Lease Line: 788 ft

26. Total Acres in Lease: 321

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26+0/0	16+0/0	39.7	0	100	50	100	0
SURF	12+1/4	9+5/8	36	0	1,950	590	1,950	0
1ST	8+3/4	7+0/0	32	1850	8,017	550	8,017	1,850

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments This will be a Monitor well for Scientific data. The cuttings will be taken by a certified transport company to a certified disposal facility. Spacing is set on the March docket, included in this application is a request to amend order # 535-246

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Justin Carlile

Title: Regulatory Specialist Date: _____ Email: justin.carlile@conocophillips.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy_MTO' located at: W:\Inetpub\Net\Report\policy_mto.rdl. Please check the

Attachment Check List

Att Doc Num	Name
400383994	OTHER
400384397	PLAT

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Site Specific	<p>ConocoPhillips Groundwater Monitoring Program</p> <p>ConocoPhillips has adopted the Colorado Oil and Gas Association (COGA) voluntary groundwater testing program to establish baseline groundwater quality conditions around new oil well locations in their leased area. The sampling program will allow the company (ConocoPhillips) to evaluate the groundwater conditions before drilling a well and also to monitor water quality afterward.</p> <p>The program will be in accordance with the guidance set forth in the Voluntary Baseline Groundwater Quality Sampling Program last updated on November 15, 2011. Under the sampling protocol, water samples would be collected from the two closest groundwater sources with reasonable access. The sample points, permitted or registered wells, would located within ½ mile of the proposed well surface location.</p> <p>Sampling will be conducted based on the landowner granting access to the well location and agreeing to have the laboratory analytical results submitted to COGCC for posting to a database viewable by the public.</p> <p>Samples will be analyzed for the constituents listed in Table 1 of the Groundwater Sampling and Analytical Program.</p>

Total: 1 comment(s)