

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400369196

Date Received:

02/04/2013

PluggingBond SuretyID

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Mary Pobuda Phone: (303)312-8511 Fax: (303)291-0420

Email: mpobuda@billbarrettcorp.com

7. Well Name: CVR Well Number: 5-63-32-25H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11173

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 32 Twp: 5N Rng: 63W Meridian: 6

Latitude: 40.355130 Longitude: -104.468650

Footage at Surface: 2349 feet FNL/FSL 230 feet FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4578 13. County: WELD

14. GPS Data:

Date of Measurement: 12/13/2012 PDOP Reading: 1.7 Instrument Operator's Name: Wyatt Hall

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL
2275 FNL 500 FWL 2275 FNL 500 FEL
Sec: 32 Twp: 5N Rng: 63W Sec: 32 Twp: 5N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 257 ft

18. Distance to nearest property line: 230 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 70 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara-Codell	NB-CD		320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20040097

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached lease map.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	65	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	800	430	800	0
1ST	8+3/4	7	26	0	6,856	570	6,856	0
1ST LINER	6+1/8	4+1/2	11.6	6000	11,173			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Please note that this well will produce from multiple leases, the "Total acres in the lease" or question #25 is referring to the lease where the well TD's. This well is an exception location, attached are waivers from the surface owner (318Aa & 318Ac). Rule 318A.m. of the COGCC rules and regulations does not allow horizontal wells to be drilled within 150 feet of another well unless this requirement is waived by the operator of the encroached upon well(s). BBC is the operator of the encroached upon well(s) so no waiver is attached. The proposed spacing unit is a 320 in the S2/N2 N2/S2.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Mary Pobuda

Title: Permit Analyst

Date: 2/4/2013

Email: mpobuda@billbarrettcorp.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 2/28/2013

API NUMBER

05 123 36898 00

Permit Number: _____

Expiration Date: 2/27/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice prior to spud via electronic Form 42.
- 2) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

Att Doc Num	Name
1792715	WAIVERS
1792721	WAIVERS
2485546	SURFACE CASING CHECK
400369196	FORM 2 SUBMITTED
400369200	DIRECTIONAL DATA
400369202	WELL LOCATION PLAT
400369203	DEVIATED DRILLING PLAN
400369210	PROPOSED SPACING UNIT
400369211	EXCEPTION LOC REQUEST
400369339	LEASE MAP
400377677	EXCEPTION LOC WAIVERS

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review completed. No LGD or Public comments.	2/27/2013 7:08:37 AM
Permit	Received waiver for Rule 318A.m.	2/27/2013 7:07:59 AM
Engineer	Evaluated existing wells within 500' of proposed directional.	2/15/2013 11:29:29 AM
Permit	Requested letter for Rule 318A.m. also it appears the this wellbore intersects with another Bill Barrett wellbore.	2/11/2013 8:32:11 AM
Permit	This form has passed completeness.	2/5/2013 11:02:17 AM

Total: 5 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)