



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 601157

Date	11-23-12	Well Owner	Kerr McGee	Well No.	29N-9HZ	Lease	Reigle
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (McJor 44)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	900		
Surface	95' LSG 36" 13 1/2" Hole	Bottom of Surface		Fl.	898		
Plug		Plug Landed @	858	Fl.	Time On	0400	
Production		Pipe Landed @	898	Fl.	Plug Down	0745	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	670	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	120	Miles		
Fuel Surcharge	120	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	0643 0649		
Disp. Rate 5 BPM	Mixing	0649 0724		
Slurry Vol. 1.32 <sup>5</sup> Cu.Ft./Sk	Change Valves	0729 0732		
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0732 0745		
Water/Cement 6.25 Gal/SK				
Water Temp. 62°F				
Total Slurry Vol. 157.5	BBLs Cement			
Landed Plug @ 860	PSI/Final Lift @ 410	PSI		
Pre-Flush W/ 30	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ 66.3	BBLs H <sub>2</sub> O	State CO 2.9%	Tax	
Circulate 5	BBLs Cement		Total	Ed Asuchak

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		40	WBS/WO/CC	2075928	
1214/1217		Bulk Truck		40/40	G/L Accl.	80012090	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Joshua, Tucker

Received By Randy Case  
Customer or His Agent