

FORM  
2

Rev  
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400377405

Date Received:

02/06/2013

PluggingBond SuretyID

20120011

APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

3. Name of Operator: NIGHTHAWK PRODUCTION LLC

4. COGCC Operator Number: 10399

5. Address: 1805 SHEA CENTER DR #290

City: HIGHLANDS RANCH State: CO Zip: 80129

6. Contact Name: KYLA VAUGHAN Phone: (505)326-2107 Fax: ()

Email: KVAUGHAN@LTENV.COM

7. Well Name: TAOS Well Number: 1-10

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8600

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 10 Twp: 6S Rng: 54W Meridian: 6

Latitude: 39.547420 Longitude: -103.419820

Footage at Surface: 1091 feet FNL/FSL FNL 852 feet FEL/FWL FEL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 5213 13. County: LINCOLN

14. GPS Data:

Date of Measurement: 12/22/2012 PDOP Reading: 2.5 Instrument Operator's Name: KEITH WESTFALL

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1186 FNL 649 FEL FEL Bottom Hole: FNL/FSL 1186 FNL 649 FEL FEL  
Sec: 10 Twp: 6S Rng: 54W Sec: 10 Twp: 6S Rng: 54W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 852 ft

18. Distance to nearest property line: 852 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1341 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ARBUCKLE	ABCK			
ATOKA	ATOK			
CHEROKEE	CHRK			
LANSING KANSAS CITY	LGKC			
MISSISSIPPIAN	MSSP			
MORROW	MRRW			
SPERGEN	SPGN			
WARSAW	WRSW			
WOLFCAMP	WFCMP			

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T6S, R54W, SECTION 10: E/2

25. Distance to Nearest Mineral Lease Line: 649 ft 26. Total Acres in Lease: 320

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method:  Land Farming  Land Spreading  Disposal Facility Other: BACKFILL WHEN DRY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	300	197	300	0
1ST	7+7/8	5+1/2	17	0	8,600	584	8,600	3,619

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments NO SURFACING CASING WILL BE USED.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: KYLA VAUGHAN

Title: AGENT FOR NIGHTHAWK Date: 2/6/2013 Email: KVAUGHAN@LTENV.COM

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 2/28/2013

<b>API NUMBER</b>
05 073 06520 00

Permit Number: \_\_\_\_\_ Expiration Date: 2/27/2015

**CONDITIONS OF APPROVAL, IF ANY:**

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

- 1) Provide 48 hour notice prior to spud via electronic Form 42.
- 2) Provide cement coverage of Cheyenne-Dakota interval: 100' below Cynn to 50' above Dkta. (Estimate 4830'-4540') Run and submit CBL to verify all cemented intervals.
- 3) If well is a dry hole set plugs at the following depths: 40 sks cement +/- 50' above the Spergen, 40 sks cement across any DST w/ show, 40 sks cement 100' below base of Cynn, 40 sks cement 50' above top of Dkta, 50 sks cement from 50' below surface casing shoe up into surface casing, 15 sks cement in top of surface casing, cut 4 ft below GL, weld on plate, 5 sks cement each in rat hole and mouse hole.

**Applicable Policies and Notices to Operators**

Notice Concerning Operating Requirements for Wildlife Protection.

**Attachment Check List**

Att Doc Num	Name
2485540	SURFACE CASING CHECK
400377405	FORM 2 SUBMITTED
400377406	WELL LOCATION PLAT
400377408	TOPO MAP
400377409	PROPOSED BMPs
400377699	DEVIATED DRILLING PLAN
400378244	SURFACE AGRMT/SURETY

Total Attach: 7 Files

**General Comments**

User Group	Comment	Comment Date
Permit	Final review completed; no public comment received.	2/28/2013 9:48:33 AM
LGD	County Permit #1319	2/8/2013 8:48:14 AM
Permit	Passed completeness.	2/7/2013 6:46:56 AM

Total: 3 comment(s)

## BMP

<u>Type</u>	<u>Comment</u>
Construction	SEE ATTACHED

Total: 1 comment(s)