

## WELLBORE DIAGRAM

Directions: WCR 29, N to WCR 78, 0.5 mi W into Location

### Bayswater Exploration & Production

#### Coalbank Creek 10-20

NESE Sec 20 T7N R66W

SHL: 1722' FSL, 216' FEL

BHL: 1980' FSL, 2031' FEL

Weld County CO

05-123-35318

Updated

02/25/13

JRR

G.L.= 4944

K.B.= 4960

16

8-5/8" 24# set at 860' (12-1/4" hole)

Cmt'd w/ 610 sx to Surf.

TOC: 1392'

CBL

Frac 8/07/12 with 268,127 gals slick H2O and 180160 # 30/50

Perf: 7765-7779', 4 spf, 19 gm, 120 deg ph .42" EHD

<<

>>

PBTD= 7,903'

TD MD= 7,950'

TD VD= 7,627'

4-1/2" 11.6# CSG @ 7925' (7-7/8" O.H.)

Cmt'd w/ 900 sx