

WELLBORE DIAGRAM

Bayswater E&P LLC

Baldrige 17-1

SWSE Sec 36-T7N-R67W

SHL: 243' FSL, 2184' FEL

BHL: 1366' FNL, 1345' FEL

Weld County CO

05-123-35730

Updated

02/25/13

JRR

Directions:

Hwy 85 N to Hwy 392, W
to WCR 27, N to WCR 74,
1.25 mi W, N into

G.L.= 4876

K.B.= 4892

16

8-5/8" 24# set at 606' (12-1/4" hole)

Cmt'd w/ 235 sx to Surf.

TOC: 1200'

CBL

<<

>>

PBTD= 7,749'

TD MD= 7,775'

TD TVD= 7,459'

Codell 7612-7627, 4 spf 60 holes

Frac on 11/16/12 with 278,590 gals Slickwater and 180,000# 30/50 White

4-1/2" 11.6# CSG @ 7762' (7-7/8" O.H.)

Cmt'd w/ 225 sx lead, 11 ppg; 452 sx middle, 12.5 ppg; 238 sx tail, 14.6 ppg