

WELLBORE DIAGRAM

Bayswater E&P LLC

Schneider 16-36

SWSE Sec 36-T7N-R67W

SHL: 243' FSL, 2124' FEL

BHL: 645' FSL, 678' FEL

Weld County CO

05-123-35724

Updated

02/25/13

JRR

Directions:

Hwy 85 N to Hwy 392, W to

WCR 27, N to WCR 74,

1.25 mi W, N into

G.L.= 4877

K.B.= 4893

16

8-5/8" 24# set at 607' (12-1/4" hole)
Cmt'd w/ 430 sx to Surf.

TOC: 900'
CBL

CODL: 7577-7594', 4 spf

Frac on 12/6/12 with 277,943 gals and 180,480# 30/50 white

4-1/2" 11.6# CSG @ 7732' (7-7/8" O.H.)

Cmt'd w/ 270 sx lead, 11 ppg; 455 sx middle, 12.5 ppg; 220 sx tail, 14.6 ppg

PBTD= 7,715'

TD MD= 7,745'

TD TVD= 7,487'