



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601006

Date	9-19-2012	Well Owner	Kerr McGee	Well No.	310-2942	Lease	RAYMOND
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAY-2942)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	930		
Surface	95% 050 314 12 1/4 H/W	Bottom of Surface		Fl.	917		
Plug		Plug Landed @	877	Fl.	Time On	0500	
Production		Pipe Landed @	917	Fl.	Plug Down	0745	
Description		Qty.	Meas.	Unit Price	Amount		
Set Up Charge		1					
Cement Neat	TYPE III	680	SKS				
Poz. Mix							
Calcium Chloride		2.5	%				
Gel % Flo-Cete 1/4 # Per Sack							
Mileage Charge		114	Miles				
Fuel Surcharge		114	Miles				
Additional Cement			SKS				
Mixing Rate	4 BPM	Pre-Flush	0144	0650			
Disp. Rate	5 BPM	Mixing	0450	0729			
Slurry Vol.	1.32 Cu.Ft./Sk	Change Valves	0739	0732			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0732	0745			
Water/Cement	6.25 Gal/SK						
Water Temp.	60						
Total Slurry Vol.	159.9	BBLs Cement					
Landed Plug @	800	PSI/Final Lift @	300	PSI			
Pre-Flush W/	20	BBLs H <sub>2</sub> O		Tax Reference Code	Sub Total		
Displace W/	67.7	BBLs H <sub>2</sub> O		State	CO 2.9%	Tax 80012090	
Circulate	5	BBLs Cement			Total		
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		39			
1207/1211		Bulk Truck		38/39			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Adams / Jessica

Received By

Brian Ray  
Customer or His Agent