

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400385594

Date Received:

03/06/2013

PluggingBond SuretyID

20090078

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐Refiling ☐Sidetrack ☐

3. Name of Operator: PDC ENERGY INC

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Julie Webb Phone: (303)339-4400 Fax: (303)399-4399

Email: jwebb@progressivepcs.net

7. Well Name: O Investment Properties

Well Number: 6Y-401

8. Unit Name (if appl):

Unit Number:

9. Proposed Total Measured Depth: 11587

## WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 6 Twp: 6N Rng: 65W Meridian: 6

Latitude: 40.511090

Longitude: -104.697700

Footage at Surface: 500 feet FNL/FSL FSL 236 feet FEL/FWL FEL

11. Field Name: Eaton

Field Number: 19350

12. Ground Elevation: 4777

13. County: WELD

14. GPS Data:

Date of Measurement: 01/11/2013 PDOP Reading: 2.6 Instrument Operator's Name: Adam Kelly

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
734 FSL 150 FEL 500 FNL 150 FEL  
Sec: 6 Twp: 6N Rng: 65W Sec: 6 Twp: 6N Rng: 65W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 285 ft

18. Distance to nearest property line: 236 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 450 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL		320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 1999008623a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Sec 6 T6N R65W See attached mineral lease map. Horizontal wellbore crosses lease lines within drilling and spacing unit; distance to lease line is 0'; distance to unit boundary is 150'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 82

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	875	830	875	0
1ST	8+3/4	7	26	0	7,706	650	7,706	500
1ST LINER	6+1/8	4+1/2	11.6	6402	11,587			

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments 7" casing string will be cemented to at least 200' above Niobrara, around 500' from surface. CBL will only be run in the vertical section of the wellbore. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waivers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 320 acres, E2E2 of Sec 6 T6N R65W and W2W2 of Sec 5 T6N R65W. Proposed spacing unit map and 30-day certificate is attached.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julie Webb

Title: Regulatory Analyst Date: 3/6/2013 Email: jwebb@progressivepcs.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy\_NTO' located at: W:\netpub\Net\Reports\policy\_nto.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400385594	FORM 2 SUBMITTED
400385759	MINERAL LEASE MAP
400385760	DEVIATED DRILLING PLAN
400385761	DIRECTIONAL DATA
400385762	WELL LOCATION PLAT
400385763	EXCEPTION LOC WAIVERS
400385765	30 DAY NOTICE LETTER
400385769	EXCEPTION LOC REQUEST
400385789	PROPOSED SPACING UNIT

Total Attach: 9 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)