

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400387028

Date Received:

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER Lateral
SINGLE ZONE MULTIPLE COMMINGLE

Refiling
Sidetrack

PluggingBond SuretyID

20100227

3. Name of Operator: CONOCO PHILLIPS COMPANY

4. COGCC Operator Number: 19160

5. Address: P O BOX 2197

City: HOUSTON State: TX Zip: 77252-2197

6. Contact Name: Justin Carlile Phone: (432)688-9165 Fax: (432)688-6019

Email: justin.carlile@conocophillips.com

7. Well Name: Zukowski 17 Well Number: 1H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11920

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 17 Twp: 4S Rng: 64W Meridian: 6

Latitude: 39.707844 Longitude: -104.565653

Footage at Surface: 863 feet FNL 250 feet FNL 250 feet FNL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5649.5 13. County: ARAPAHOE

14. GPS Data:

Date of Measurement: 10/25/2012 PDOP Reading: 1.6 Instrument Operator's Name: Robert Kay

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 660 FNL 816 FEL 660 FNL 480 FNL
Bottom Hole: 660 FNL 480 FNL
Sec: 17 Twp: 4S Rng: 64W Sec: 17 Twp: 4S Rng: 64W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 832 ft

18. Distance to nearest property line: 250 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1232 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-155	640	NENE

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

NENE, Township 4 South, Range 64 West, Section 17: ALL

25. Distance to Nearest Mineral Lease Line: 480 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24+0/0	16+0/0	39.7	0	100	50	100	0
SURF	12+1/4	9+5/8	36	0	1,970	590	1,970	0
1ST	8+3/4	7+0/0	32	1970	7,902	540	7,902	1,870
1ST LINER	6+0/0	4+1/2	13.5	7902	11,920			

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Cuttings will be taken by a certified transport company and disposed of at a certified disposal facility. The lateral hole will be produced interval of this well, pilot hole is there to aid the building of the curve.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Justin Carlile

Title: Regulatory Specialist Date: _____ Email: justin.carlile@conocophillips.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTO' located at: \\Inetpub\NetReports\policy_nto.rdl. Please check the

Attachment Check List

Att Doc Num	Name
400388379	PLAT
400388382	DEVIATED DRILLING PLAN
400388870	DIRECTIONAL DATA

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Site Specific	<p>ConocoPhillips Groundwater Monitoring Program</p> <p>ConocoPhillips has adopted the Colorado Oil and Gas Association (COGA) voluntary groundwater testing program to establish baseline groundwater quality conditions around new oil well locations in their leased area. The sampling program will allow the company (ConocoPhillips) to evaluate the groundwater conditions before drilling a well and also to monitor water quality afterward.</p> <p>The program will be in accordance with the guidance set forth in the Voluntary Baseline Groundwater Quality Sampling Program last updated on November 15, 2011. Under the sampling protocol, water samples would be collected from the two closest groundwater sources with reasonable access. The sample points, permitted or registered wells, would located within ½ mile of the proposed well surface location.</p> <p>Sampling will be conducted based on the landowner granting access to the well location and agreeing to have the laboratory analytical results submitted to COGCC for posting to a database viewable by the public.</p> <p>Samples will be analyzed for the constituents listed in Table 1 of the Groundwater Sampling and Analytical Program.</p>

Total: 1 comment(s)