

US ROCKIES REGION

Anadarko Daily Summary Report

Well: ELKHORN CO GU 1

Project: COLORADO-WELD

Site: ELKHORN CO GU 1

Rig Name No: BASIC 1549/1549, TR DENNER 3/3,
CONCORD 6/6

Event: CONST- CAP WELL WORK

Start Date: 8/14/2012

End Date: 12/21/2013

Spud Date: 8/30/1973

Active Datum: RKB @5,044.00usft (above Mean Sea Level)

UWI: 0/2/N/67/W/21/0/NESW/6/0/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	09/06/2012		RU Cable & pull BS. Tag fill @ 8179'. RD Cable.
2	09/07/2012		MIRU Basic 1549. Kill well. ND well head. NU BOP. TOO H & tally tbg. PU 3 7/8" bit, 4 1/2" csg scraper & TIH. TOO H & EMI tbg. Had 252 good jts & 3 bad jts. SI. SDFN.
3	09/10/2012		Kill well. RU PSI & set CIBP @ 7570'. Shoot 3 squeeze holes @ 7310' (.40"). PU pkr & TIH. Set pkr @ 7355 & test CIBP to 1000 psi. Reset pkr @ 7260'. Pump into perfs @ 2 bpm @ 600 PSI. Release pkr & TOO H. Set retainer @ 7200'. TIH & stiing into retainer.
4	09/11/2012		RU Baker Hughes & pump 135 sks 50/50 poz through perfs @ 7310'. Sting out of retainer & TOO H. SI. SDFN.
5	09/12/2012		Replaced 2000# wellhead w/5000# wellhead
6	09/13/2012		RU PSI & run CBL from 7137' to 6450'. Tagged @ 7156'. Cmt top @ 6665'. PU NC/SN & TIH. Land w/224 jts tbg @ 7055'. ND BOP. Test csg to 1000 psi. OK. NU well head. SI. RDMO Basic 1549.
1	12/14/2012		CREW TO LOC, SPOT IN BEAM, RIG PUMP + TANK, TP 0/ CP 0, ND WH, NU BOP, TOO H 224 JTS, LD SN/NC, PU 3 7/8 BIT, RIH TAG CIRC @ 7156, LD 1 JT, SDFN.
2	12/17/2012		CREW TO LOC, WARM UP EQUIP, TP 0/ CP 0, PU RIH 1 JT, EST CIRC, TAG CIRC @ 7166 W/ 228 JTS + MILL TO 7228, CIRC CLEAN, SDFN.
3	12/18/2012		CREW TO LOC, TP 0/ CP 0, WARM UP EQUIP, TOO H LD BIT, PU NEW BIT RIH TAG CIRC, EST CIRC, FINISH MILL OUT CIRC, CONTIN RIH TAG CIBP @ 7570, CIRC CLEAN, MILL OUT PUSH TO 8175 W/ 260 JTS, TOO H LD BIT, SDFN.
4	12/19/2012		CREW TO LOC, TP 0/ CP 0, WARM UP EQUIP, PU SN/NC RIH LAND TBG @ 8062 KB W/ 256 JTS 2 3/8 TBG, RIH BROACH TBG, ND BOP, NU WH, RDMO.
102	12/21/2012		TIME ON: 11:45, ROUTE: S15, WINS: 74825, PROJECT TYPE: CCW, PROD: CD/JSND, TP: 350, CP: 325, CHOKE: N/A, BATT #: 34002696, GATHERER: KMG, STAT #: 007687, LINE #: 16-91-4, COMMENTS: RWTP UP TBG AFTER HZ UN-SAFETY PREP
100	01/04/2013		MIRU TR Denner rig #3 TP 210 Cp 100 SC 0 IFL 7000'. Blew down and broache dtbfg. Swabbed 7 bbl water. SI. FFL 7200' TP 60 Cp 175 SDFN
101	01/05/2013		Crew travel TP 340 CP 340 IFL 7500'. Blew tbg down. Swabbed 2 bbl 80% oil. SI. TP 60 CP 200 RDMO TR Denner rig #3