

**KERR-MCGEE ROCKY MOUNTAIN CORP**

**MOSER 5-4  
SW NW 4 2N 65W -- --  
WELD,COLORADO  
03/08/2013**

**AREA: S4      ROUTE: S41    Spud: 12/02/2005    WINS No.: 75319    AFE/WO#: 88323981    API#: 0512323350**

**GL: 4876    KB: 4888    MTD: 7849    TVD: 7849    LOG MD: 7821    PBMD: 7814    PBTVD: 7814**

**Directions:    WCR 41 AND WCR 26, 1/2 MILE SOUTH, EAST INTO**



<u>HOLE SECTIONS</u>		<u>Size</u>	<u>Top</u>	<u>Btm</u>	<u>TD Date</u>			
SURFACE		12.25	12	822	12/03/2005			
PRODUCTION		7.88	822	7879	12/07/2005			
<u>TUBULARS</u>		<u>Tool Type</u>	<u>Joints</u>	<u>Size</u>	<u>Weight</u>	<u>Grade</u>	<u>Thread</u>	<u>Top D</u> <u>Bottom D</u>
SURFACE CASING		Casing	18	8.63	24	J-55	STC	12      812
PRODUCTION CASING		Casing	187	4.50	11.6	I-80	LTC	12      7814
			1	4.50				7814      7815
		Casing	1	4.50	11.6	I-80	LTC	7815      7838
		Casing Guide Shoe	1	4.50				7838      7839
PRODUCTION TUBING		Wellbore Equipment	245	2.38		J-55		10      7645
		Wellbore Equipment	1	2.38				7645      7646
		Wellbore Equipment	1	2.38				7646      7647
<u>CEMENT JOBS</u>		<u>Stage</u>	<u>Sacks</u>	<u>Cement Jobs</u>		<u>Top D</u>	<u>Btm D</u>	<u>cbl</u>
SURFACE CASING		STAGE 1	570	NEAT		12	812	No
PRODUCTION CASING		STAGE 1 LEAD	240	LITE		3940	5426	Yes
		STAGE 1 MIDDLE	100	LITE		5426	5670	Yes
		STAGE 1 TAIL	270	50/50 POZ-MIX		5670	7838	Yes
PRODUCTION CASING		ONE INCH JOB				710	3910	Yes
<u>PERFORATIONS</u>		<u>Formation</u>	<u>Zone</u>	<u>Top</u>	<u>Btm</u>	<u>Date</u>	<u>Reason</u>	<u>Comments</u>
		CODELL		7218	7232	12/16/2005	PRODUCTION	
		J SAND		7672	7675	11/01/2006	PRODUCTION	
		J SAND		7678	7690	11/01/2006	PRODUCTION	
		J SAND		7705	7740	11/01/2006	PRODUCTION	

Comments: